

INDEX		
DRAWING NO.	SHEET NO.	DESCRIPTION
1	1	COVER SHEET
2-01	2	INDEX / GENERAL NOTES
3-01	3	REVISION SUMMARY
5-01	4	TYPICAL SECTIONS
6-01	5	SUMMARY OF QUANTITIES
7-01	6	QUANTITIES REQUIRED BY AMENDMENT SHEET
8-01	7	QUANTITIES REQUIRED ON CONSTRUCTION SHEET
9-01	8	DETAILED ESTIMATE
13-01	9	CONSTRUCTION PLAN SHEET
19-01-19-04	10-13	CONSTRUCTION STAGING PLAN SHEETS
20-01	14	TRAFFIC CONTROL DETAIL
26-01	15	SIGNING AND MARKING PLAN
35-01-35-03	16-18	BRIDGE PLANS
40-01	19	CONSTR DETAILS - SIGN PLATES (T-01) (01-00)
40-02	20	CONSTR DETAILS - DETAILS OF TIMBER POLE ERECTION FOR OVERHEAD SIGNS (T-03D) (01-00)
40-03	21	CONSTR DETAILS - PVM'T MARKING PLACEMENT ON NON-LIMITED ACCESS RWAY (T-11A) (01-00)
40-04	22	CONSTR DETAILS - DETAILS OF PAVEMENT MARKING ARROW LOCATION (T-12A) (01-00)
40-05	23	CONSTR DETAILS - DETAILS OF PAVEMENT MARKINGS - ARROWS (T-12B) (04-00)
40-06	24	CONSTR DETAILS - RAISED PVM'T MARKER LOCATION NON-LIMITED ACCESS (T-15A) (01-04)
40-07	25	CONSTR DETAILS - DETAILS OF RAISED PAVEMENT MARKERS (T-15C) (01-00)
41-01	26	GA STD 3054 - END POST AND END POST GUARDRAIL ATTACHMENT DETAIL (09-02)
41-02	27	GA STD 3901 - BAR BENDING DETAILS (08-69)
41-03	28	GA STD 4000W- GUARDRAIL WARRANT GUIDES (12-99)
41-04	29	GA STD 4010 - "W" BEAM GUARDRAIL (07-97)
41-05	30	GA STD 4011A- POST & O/S BLOCKS "W" & "T" BEAM GUARDRAIL (12-01)
41-06	31	GA STD 4012D- GUARDRAIL ANCHORAGE TP 1 (07-02)
41-07	32	GA STD 4013 - GUARDRAIL ANCHORAGE TP 5 & 6 (06-98)
41-08	33	GA STD 4040 - GUARDRAIL ANCHORAGE TP 12 (07-97)
41-09	34	GA STD 4052 - GUARDRAIL LOCATION DETAILS FOR UNDIVIDED HIGHWAYS & ROADS (10-97)
41-10	35	GA STD 4270 - STD. "T" BEAM GUARDRAIL (11-99)
41-11	36	GA STD 9100 - TRAFFIC CONTROL GEN. NOTES, STD. LEGEND, MISC. DETAILS (04-01)
41-12	37	GA STD 9102 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE ON TWO-LANE HIGHWAY(07-99)
	37	TOTAL SHEETS

GENERAL NOTES

1. THE CONTRACTOR SHALL BE REQUIRED TO USE THE UPC ONE-CALL CENTER TELEPHONE NUMBER FOR UTILITY LOCATIONS PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR'S ATTENTION IS CALLED TO SUB-SECTION 105.06 "COOPERATION WITH UTILITIES".

**THE CONTRACTOR SHALL ADHERE TO
THE CALL BEFORE YOU DIG LAW
BY CALLING THE UTILITIES
PROTECTION CENTER**

Dig | Safely.
1-800-282-7411
770-623-4344

THE FOLLOWING UTILITIES HAVE FACILITIES IN THE PROJECT AREA:

ALLTEL
(706) 782-5001

HABERSHAM EMC
(706) 754-2114

LAKE BURTON CABLE TELEVISION
(706) 782-7080

2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.
3. NOTICE OF INTENT IS NOT REQUIRED.
4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.
6. THE CONTRACTOR SHALL REPLACE IN KIND ANY VEGETATION OR LANDSCAPING DAMAGED DURING CONSTRUCTION. COST SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR GRADING COMPLETE.
7. THERE IS NO SUITABLE SITE TO DISPOSE OF BRIDGE PARTS WITHIN THE RIGHT-OF-WAY.
8. ANY REQUIRED PERMANENT OR TEMPORARY EROSION CONTROL DEVICES AND PERMANENT OR TEMPORARY GRASSING WILL NOT BE MEASURED SEPERATELY FOR PAYMENT. PAYMENT FOR THESE ITEMS WILL BE INCLUDED IN THE OVERALL BID FOR GRADING COMPLETE.
9. THE CONTRACTOR SHALL COORDINATE THE WORK AND ANY OTHER REQUIREMENTS OVER LAKE BURTON WITH GEORGIA POWER AND ANY OTHER AGENCY WITH GOVERNING AUTHORITY OVER THE LAKE.
10. THE COST FOR GUARDRAIL REMOVAL AND ANY GRADING REQUIRED FOR NEW GUARDRAIL SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR GRADING COMPLETE.

JBT J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE
INDEX\GENERAL NOTES

PROJECT: CSSTP-M002-00 (788)
COUNTY: RABUN

DRAWING No.
2-01