TRAFFIC CONTROL
CSSTP-M002-00(788)

TOTAL LUMP SUM

GRADING COMPLETE
CSSTP-M002-00(788)

TOTAL LUMP SUM

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3

TOTAL 2

TRAFFIC SIGNAL INSTALLATION NO. 1

TOTAL LUMP SUM

TRAFFIC SIGNAL INSTALLATION NO. 2

TOTAL LUMP SUM

PAVEMENT MARKERS (EACH)

LOCATION	REFLECTIVE-RAISED		
	YELLOW TYPE 1	CLEAR TYPE 2	CLEAR/RED TYPE 3
SR 2	26		
TOTALS	26		

NOTE: PAVEMENT MARKERS SHALL BE SPACED 80 FEET APART.

TRAFFIC STRIPE

DESCRIPTION	UNIT	QUANTITY PREFORMED	QUANTITY THERMOPLASTIC
STA. 411+40 - 412+90			
5" SOLID WHITE	LIN FEET	0	235
5" SOLID YELLOW	LIN FEET	0	170
5" SKIP WHITE	GR LIN FT	0	0
10" SOLID WHITE	LIN FEET	0	0
STA. 412+90 - 417+92			
5" SOLID WHITE	LIN FEET	1004	0
5" SOLID YELLOW	LIN FEET	1004	0
5" SKIP WHITE	GR LIN FT	0	0
10" SOLID WHITE	LIN FEET	0	0
STA. 417+92 - 420+80			
5" SOLID WHITE	LIN FEET	0	576
5" SOLID YELLOW	LIN FEET	0	576
5" SKIP WHITE	GR LIN FT	0	0
10" SOLID WHITE	LIN FEET	0	0
VICKERS ROAD			
5" SOLID WHITE	LIN FEET	0	40
5" SOLID YELLOW	LIN FEET	0	80
5" SKIP WHITE	GR LIN FT	0	0
10" SOLID WHITE	LIN FEET	0	0
24" SOLID WHITE	LIN FEET	0	24
TOTALS			
5" SOLID WHITE	LIN FEET	1004	851
5" SOLID YELLOW	LIN FEET	1004	826
5" SKIP WHITE	GR LIN FT	0	0
10" SOLID WHITE	LIN FEET	0	0
24" SOLID WHITE	LIN FEET	0	24

SURFACING QUANTITES

ITEMS	UNIT	BRIDGE NO. 1 SR 2 STAGE 1	SR 2 STAGE 2	SR 2 FINISHING	VICKERS ROAD STAGE 1	VICKERS ROAD STAGE 2	VICKERS ROAD FINISHING	AS DIRECTED BY ENGINEER	TOTALS
GR AGGR BASE CRS, INCL MATL	TN				110			20	130
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	23	23					4	50
RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN			103	23			14	140
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN			126	36			18	180
BITUM TACK COAT	GL	91	91	182	20			16	400
MILL ASPH CONC PVMT, VARIABLE DEPTH	SY			1516				84	1600

ARROWS (EACH)

DESCRIPTION	QUANTITY PAINT	QUANTITY THERMOPLASTIC
TYPE 1		
TYPE 2		2
TYPE 3		
TYPE 4		
TYPE 7		

NOTE: ALL ARROWS SHALL BE WHITE UNLESS OTHERWISE SPECIFIED. SEE PLANS FOR LOCATION.

GUARDRAIL QUANTITIES
GA. STDS. 4010, 4011-A, 4012-D,• 4013,••• 4040,•• 4052, 4270

GUARDRAIL LOCATION	SIDE	TP "W" LIN FT	TP "T" LIN FT	ANCHORAGES TP 1 •	TP 6 •••	TP 12 ••
412+04.00	LT			1		
412+04.00 - 412+69.00	LT	65				
412+69.00 - 412+89.65	LT		20.65		1	
412+34.00	RT					1
412+34.00 - 412+69.00	RT	35				
412+69.00 - 412+89.65	RT		20.65		1	
417+92.35 - 418+13.00	LT		20.65		1	
418+13.00 - 418+78.00	LT	65				
418+78.00	LT					1
417+92.35 - 418+13.00	RT		20.65		1	
418+13.00 - 419+13.00	RT	100				
419+13.00	RT			1		
AS DIRECTED BY ENGINEER		35				
TOTALS		300	84	2	4	2

JBT J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

SUMMARY OF QUANTITIES

PROJECT: CSSTP-M002-00 (788)
COUNTY: RABUN

DRAWING No. 6-01

GPLM

...\dgn\rabchy\m002788qty.dgn 8/19/2005 8:51:05 AM