DETAILED ESTIMATE

ITEM NO.	ITEMS	UNIT	QUANTITY
	ROADWAY		
150-1000	TRAFFIC CONTROL - PROJECT NO CSSTP-M002-00(788)	LS	LUMP
210-0100	GRADING COMPLETE - PROJECT NO CSSTP-M002-00(788)	LS	LUMP
310-1101	GRADED AGGR BASE CRS, INCL MATL	TN	130
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	50
402-3131	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	140
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TN	180
413-1000	BITUM TACK COAT	GL	400
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	1600
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	2
641-1100	GUARDRAIL, TP T	LF	84
641-1200	GUARDRAIL, TP W	LF	300
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	2
641-5006	GUARDRAIL ANCHORAGE, TP 6	EA	4
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	2
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 1	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO - 2	LS	LUMP
	SIGNING & MARKING		
653-0120	THERMOPLASTIC PVMT MARKING, ARROW, TP 2	EA	2
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	LF	851
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	826
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	24
654-1001	RAISED PVMT MARKERS TP 1	EA	26
657-1054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, WHITE, TP PB	LF	1004
657-6054	PREFORMED PLASTIC SOLID PVMT MKG, 5 IN, YELLOW, TP PB	LF	1004
	BRIDGE NO. 1		
443-1000	ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO-1, BENT NO - 4	EA	1
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	84
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-1		
449-1620	LOW-DENSITY, CLOSED-CELL, X-LINKED, ETHYLENE VINYL ACETATE,	LF	42
	POLYETHYLENE COPOLYMER, NITROGEN-BLOWN SEAL, BR NO-1, BENT NO-4		
500-0100	GROOVED CONCRETE	SY	2050
504-0600	TWENTY-FOUR HOUR ACCELERATED STRENGTH CONC	CY	14
511-3000	SUPERSTR REINF STEEL, BR NO-1 (1600)	LS	LUMP
519-0400	CONCRETE OVERLAY, PORTLAND CEMENT, VARB THK	SY	2050
521-1000	PATCHING CONCRETE BRIDGE DECK	SF	100
528-0750	EPOXY SEALING OF CONCRETE CRACKS	LF	2000
535-1105	PAINT EXIST STEEL STRUCTURE, BR ID - 241-00002D-007.55E	LS	LUMP
540-1202	REMOVAL OF PARTS OF EXISTING BR, BR NO-1	LS	LUMP

J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

DETAILED ESTIMATE

PROJECT: CSSTP-M002-00 (788)
COUNTY: RABUN

DRAWING No. 9-01

GPLN