GUARDRAIL QUANTITIES
GA. STDS. 4010, 4011-A, 4022-A, 4052

GUARDRAIL "W" BEAM		TP "T"	ANCHORAGES	
LOCATION & SIDE	LIN FT	LIN FT	TP 1 *	TP 12+
545+06 LT			1	
545+06 - 548+31 LT	325			
548+31 - 548+51.65 LT		20.65		
546+00 RT				1
546+00 - 549+50 RT	350			
549+50 - 549+70.65 RT		20.65		
550+10.35 - 550+31 LT		20.65		
550+31 - 552+56 LT	225			
552+56 LT				1
551+32.35 - 551+53 RT		20.65		
551+53 - 554+78 RT	325			
554+78 RT			1	
583+45 RT				1
583+45 - 593+75 RT	1030			
593+75 - 593+95.65 RT		20.65		
584+45 - 592+45 LT	800			
592+45 - 592+65.65 LT		20.65		
595+83.35 - 596+04 LT		20.65		
596+04 - 601+29 LT	525			
601+29 LT				1
597+13.35 - 597+34 RT		20.65		
596+34 - 601+34 RT	500			
601+34 RT			1	
615+27 LT			1	
615+27 - 619+77 LT	450			
619+77 - 619+97.65 LT		20.65		
619+17 RT				1
619+17 - 621+77 RT	260			
621+77 - 621+97.65 RT		20.65		
622+56.35 - 622+77 LT		20.65		
622+77 - 625+77 LT	300			
625+77 LT				1
624+85.35 - 625+06 RT		20.65		
625+06 - 627+06 RT	200			
627+06 RT			1	
AS DIRECTED BY ENGINEER	60			
TOTALS	5350	249	5	6

* GA. STD. 4012-C
\+ GA. STD. 4040

PRECAST CONCRETE MEDIAN BARRIER
METHOD 3 - STD. 4960 & 4961

LOCATION	LIN. FT.
AS DIRECTED BY ENGINEER	5800
TOTAL	5800

PRECAST CONCRETE MEDIAN BARRIER
METHOD 4 - STD. 4960 & 4961

LOCATION	LIN. FT.
AS DIRECTED BY ENGINEER	1350
TOTAL	1350

J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

SUMMARY QUANTITIES

DRAWING No. 6-02