

INDEX		
DRAWING NO.	SHEET NO.	DESCRIPTION
1	1	COVER SHEET
2-01	2	INDEX
3-01	3	REVISION SUMMARY
5-01	4	TYPICAL SECTIONS
6-01-6-03	5-7	SUMMARY OF QUANTITIES
7-01	8	QUANTITIES REQUIRED BY AMENDMENT SHEET
8-01	9	QUANTITIES REQUIRED ON CONSTRUCTION SHEET
9-01	10	DETAILED ESTIMATE
13-01-13-13	11-23	CONSTRUCTION PLAN SHEETS
19-01-19-26	24-49	CONSTRUCTION STAGING PLAN SHEETS
26-01-26-13	50-62	SIGNING AND MARKING PLANS
35-01-35-07	63-69	BRIDGE NO. 1 PLANS
35-08-35-15	70-77	BRIDGE NO. 2 PLANS
35-16-35-22	78-84	BRIDGE NO. 3 PLANS
35-23-35-31	85-93	BRIDGE NO. 4 PLANS
35-32-35-39	94-101	BRIDGE NO. 5 PLANS
40-01	102	CONSTR DETAILS - GUARDRAIL IMPACT ATTENUATOR UNITS (G-11) (03-01)
40-02	103	CONSTR DETAILS - SUBBASES FOR APPROACH SLABS (M-2) (06-88)
40-03	104	CONSTR DETAILS - DETAILS OF PVM'T MARKING (T-11B) (01-00)
40-04	105	CONSTR DETAILS - MARKER LOCATION LIMITED ACCESS ROADWAY (T-15B) (01-00)
41-01	106	CONSTR DETAILS - DETAILS OF RAISED PVM'T MARKERS (T-15C) (01-00)
41-02	107	CONSTR DETAILS - DETAILS AND PLACEMENT OF RUMBLE STRIPS (T-19) (04-03)
41-03	108	GA STD 3054 - END POST AND END POST GUARDRAIL ATTACHMENT DETAIL (09-02)
41-04	109	GA STD 3901 - BAR BENDING DETAILS (08-69)
41-05	110	GA STD 4000W- GUARDRAIL WARRANT GUIDES (12-99)
41-06	111	GA STD 4010 - "W" BEAM GUARDRAIL (07-97)
41-07	112	GA STD 4011A- POST & O/S BLOCKS "W" & "T" BEAM GUARDRAIL (12-01)
41-08	113	GA STD 4012C- G-RAIL CONN TP 1 G-RAIL CONN AT BRIDGE/BARRIER (03-03)
41-09	114	GA STD 4012D- GUARDRAIL ANCH TP 1 (07-02)
41-20	115	GA STD 4040 - GUARDRAIL ANCH TP 12 (07-97)
41-21	116	GA STD 4051 - GUARDRAIL LOCATION DETAIL (10-97)
41-22	117	GA STD 4270 - STD. "T" BEAM GUARDRAIL (11-99)
41-23	118	GA STD 4960 - CONCRETE BARRIER - TEMPORARY (END TREATMENT OPTIONS) (02-01)
41-24	119	GA STD 4961 - DETAILS OF PRECAST TEMPORARY BARRIER (05-01)
41-25	120	GA STD 9017J- CONCRETE SPILLWAYS (ADJACENT TO APPROACH SLAB) (06-85)
41-26	121	GA STD 9017M - REINF CONC APPROACH SLAB WITH CONC BARRIER, 30 FT. LENGTH (08-99)
41-27	122	GA STD 9017R - REINF CONC APPROACH SLAB WITH ASPHALT INLAY, 30 FT. LENGTH (08-99)
41-28	123	GA STD 9037 - TYPICAL FILL DETAIL AT END OF BRIDGE (10-97)
41-29	124	GA STD 9100 - TRAFFIC CONTROL GEN. NOTES, STD. LEGEND, MISC. DETAILS (04-01)
41-30	125	GA STD 9106 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE (07-99)
	125	TOTAL SHEETS

GENERAL NOTES

THE CONTRACTOR SHALL ADHERE TO
THE CALL BEFORE YOU DIG LAW
BY CALLING THE UTILITIES
PROTECTION CENTER

Dig | Safely.

1-800-282-7411
770-623-4344

1. 
2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING COST TO BE INCLUDED IN OVERALL BID.
3. NOTICE OF INTENT IS NOT REQUIRED.
4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.
6. THE CONTRACTOR SHALL BE LIMITED TO WORKING ON TWO BRIDGES AT A TIME. THE CONTRACTOR SHALL MOVE THE CHANGEABLE MESSAGE SIGNS FROM WORK SITE TO WORK SITE AS NECESSARY.
7. THE CONTRACTOR SHALL REPLACE IN KIND ANY VEGETATION OR LANDSCAPING DAMAGED DURING CONSTRUCTION. COST SHALL BE INCLUDED IN OVERALL BID PRICE.
8. THE COST FOR GUARDRAIL REMOVAL AND ANY GRADING REQUIRED FOR NEW GUARDRAIL SHALL BE INCLUDED IN THE LUMP SUM PRICE FOR GRADING COMPLETE.



REVISION DATES	
3/7/06	

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

INDEX\GENERAL NOTES

DRAWING No.
2-01