TRAFFIC CONTROL CSNHS-M002-00(790)	
TOTAL	LUMP SUM

GRADING COMPLETE CSNHS-M002-00(790)	
TOTAL	LUMP SUM

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	
TOTAL	6

INDENTATION RUMBLE STRIPS GROUND IN PLACE (CONTINUOUS)	
TOTAL	8.5 GLM

REINFORCED CONCRETE APPROACH SLAB GA. STD. 9017-M & 9017-R

LOCATION	REINFORCED CONCRETE APPROACH SLAB INCL SLOPED EDGE & SUBBASE	CONCRETE SPILLWAY GA. STD. 9017-N	15" SLOPE DRAIN PIPE	CLASS B CONCRETE APRON
		EACH	LIN. FT	CU. YDS
480+36.05 - 480+66.05	407			
483+20.74 - 483+50.74	407			
610+90.00 - 611+20.00	223			
613+16.00 - 613+46.00	223			
TOTALS	1260			

TRAFFIC CONTROL - WORKZONE LAW ENFORCEMENT (CONTRACTOR BIDS)	
TOTAL	500 HR

TRAFFIC CONTROL IMPACT ATTENUATOR UNIT (COMPRESSION CRASH CUSHION) TYPE T-3-U-30	
TOTAL	8

TO BE USED AS DIRECTED BY THE ENGINEER

SURFACING QUANTITES

ITEMS	UNIT	BRIDGE NO. 1						BRIDGE NO. 2						BRIDGE NO. 3						BRIDGE NO. 4						BRIDGE NO. 5						AS DIRECTED BY ENGINEER	TOTALS
		MAINLINE			SHOULDER			MAINLINE			SHOULDER			MAINLINE			SHOULDER			MAINLINE			SHOULDER			MAINLINE			SHOULDER				
		STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING	STAGE 1	STAGE 2	FINISHING		
GR AGGR BASE CRS, INCL MATL	TN				2072	2072					2166	2166					2350	2350					2123	2123					2344	2344		890	23000
ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN			1488						1603						1732						1418						1466				93	7800
ASPH CONC 12.5 MM PEM, GP2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME	TN			1218			93			1312			98			1418			104			1160			96			1199			96	106	6900
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	271	271					292	292					315	315					258	258					267	267					94	2900
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN						769						804						873						789						871	94	4200
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN				1282	1282					1340	1340					1454	1454					1314	1314					1451	1451		318	14000
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN				513	513					536	536					582	582					526	526					581	581		124	5600
BITUM TACK COAT	GL	1082	1082	2164	280	280	642	1166	1166	2331	293	293	672	1260	1260	2520	318	318	727	1031	1031	2062	287	287	659	1066	1066	2132	317	317	718	173	29000
MILL ASPH CONC PVMT, VARIABLE DEPTH	SY			18032			9321			19424			9743			20993			10572			17182			9553			17762			10547	871	144000

JBT J.B. TRIMBLE, INC.
6445 Powers Ferry Road,
Suite 100
Atlanta, GA 30339

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: MAINTENANCE

SUMMARY OF QUANTITIES

DRAWING No. 6-01

\\gdot\m0020079bdat\.jan 11/8/2005 1:27:27 PM