

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSNHS-M002-00(823)	14	269

### TEMPORARY EROSION CONTROL

ITEM	UNIT	QUANTITY	AS DIRECTED BY ENGINEER	TOTAL
CONSTRUCT & REMOVE INLET SEDIMENT TRAP	EA	26	2	28
MAINTENANCE INLET SEDIMENT TRAP	EA	26	2	28
CONSTRUCT & REMOVE TEMP. PIPE SLOPE DRAIN	LF	590	10	600
CONSTRUCT & REMOVE FABRIC CHECK DAM - TP C SILT FENCE	LF	444	14	458
WATER QUALITY MONITORING AND SAMPLING	EA	2	0	2
WATER QUALITY INSPECTIONS	MO	18	0	18
TEMP SILT FENCE, TP C	LF	6442	194	6636
MAINTENANCE OF TEMP SILT FENCE, TP C	LF	3221	97	3318
CONSTRUCT AND REMOVE SILT CONTROL GATE	EA	4	0	4
MAINTENANCE OF SILT CONTROL GATE, TP I	EA	2	0	2
CONSTRUCTION EXIT	EA	6	0	6
MAINTENANCE OF CONSTRUCTION EXIT	EA	6	0	6
CONSTRUCT & REMOVE RIP RAP CHECK DAM	EA	4	1	5
MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	260	0	260

### PERMANENT EROSION CONTROL

EROSION CONTROL MAT	SY	9480	20	9500
---------------------	----	------	----	------

### GRASSING

ITEM	UNIT	QUANTITY	AS DIRECTED	TOTAL
PERMANENT GRASSING	AC	4.00	0	4.00
TEMPORARY GRASSING	AC	2.00	0	2.00
AGRICULTURAL LIME	TN	6	0	6
FERTILIZER MIXED GRADE	TN	2	0	2
FERTILIZER NITROGEN CONTENT	LB	205	6	211
MULCH	TN	60	2	62



G R E S H A M  
S M I T H   A N D  
P A R T N E R S

DATE	REVISIONS	DATE	REVISIONS

GEORGIA  
 DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 PROJECT - CSNHS-M002-00(823)  
 COUNTY - DEKALB  
 DATE SHEET 6-04