

3/17/2010 fflanders		Tue Aug 17 09:04:21 2010 \\gdot-dsn1\gocfg\resources\gdot2007_K1p.tbl		Y:\M003340 - Sta. 710+00 to 1000+00\DGN\M0033400N01.dgn		STATE GA	PROJECT NUMBER CSNHS-M003-00(340)	SHEET NO. 20	TOTAL SHEETS 414
SUMMARY OF QUANTITIES									
GRASSING							CONSTRUCTION EXIT		
DESCRIPTION	GRASSING	LIQUID LIME	AGRICULTURAL LIME	FERTILIZERS		MULCH	ITEM	UNITS	TOTALS
	AC	GAL	TN	MIXED GRADE	NITROGEN CONTENT		CONSTRUCTION EXIT	EA	8
PERMANENT	65	163	195	TN	LB	TN	MAINTENANCE OF CONSTRUCTION EXIT	EA	16
TEMPORARY	33			7		99			
DISTURBED						756			
TOTALS	98	163	195	124	6500	1050			
							WATER QUALITY		
							ITEM	UNITS	TOTALS
							WATER QUALITY MONITORING AND SAMPLING	EA	2
							WATER QUALITY INSPECTIONS	MO	24
FIELD ENGINEER'S OFFICE - TYPE 3							SILT FENCE		
TOTAL 1 EACH							ITEM	UNITS	TOTALS
							TEMPORARY SILT FENCE, TYPE A	LF	22310
							MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	11155
							TEMPORARY SILT FENCE, TYPE C	LF	25986
							MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	12993
EROSION CONTROL MATS, SLOPES							CHECK DAMS		
TOTAL 100778 SY							ITEM	UNITS	TOTALS
							CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	EA	10
							CONSTRUCT AND REMOVE FABRIC CHECK DAM - TYPE C SILT FENCE	LF	14522
							MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	7361
CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN									
TOTAL 500 LF									
TO BE USED AS DIRECTED BY ENGINEER									
BARRIER FENCE (ORANGE), 4 FT									
TOTAL 8540 LF									