Date Submitted: January 7, 2010

DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA

SPECIAL PROVISION

P. I. No. M004049
COUNTY: COWETA/ FULTON

Section 108—Prosecution and Progress

Add the following to Subsection 108.08:

C. Intermediate Completion Schedule

An overall Completion Date is established for this Project. However, it is necessary to complete certain portions of The Work at an earlier time.

For this Project, the following items of work and corresponding intermediate completion times are required:

1. Earth Shoulder Reconstruction

   Failure to complete earth shoulder reconstruction work within thirty (30) Calendar days after completion of resurfacing the roadway will result in the assessment of Liquidated Damages at a rate of $500.00 per Calendar day.

2. Cover Milled Area

   Failure to cover each milled area on same day milled and prior to opening lanes to traffic will result in the assessment of Liquidated Damages at a rate of $1,000.00 per calendar day.

3. Complete Paving Operations

   Failure to complete all paving operations (e.g., shoulder clipping, patching, asphalt shoulder widening, milling, leveling, resurfacing, etc) within one hundred twenty (120) calendar days, from the start date of any of the paving operations, will result in the assessment of Liquidated Damages at a rate of $500.00 per calendar day.

4. Single Layer Surface Treatment

   Failure to cover the surface treated areas with the leveling course the same day and prior to opening the lanes to traffic will result in the assessment of Liquidated Damages at a rate of $1,000.00 per calendar day.

5. Permanent Striping Placement

   Failure to ensure placement of permanent striping does not begin until thirty (30) calendar days after completion of the final surface course and completion within forty five (45) calendar days after completion of the final surface course will result in the assessment of liquidated damages at a rate of $1,000.00 per calendar day.

6. Traffic Loop Replacement

   Failure to replace Traffic Loops and have operational within the designated time as specified in Section 150.11 (B) will result in liquidated damages at a rate of $500.00 per hour or any part thereof.