

---

GENERAL NOTES (CONTINUED)

---

19. TEMPORARY STRIPING IS REQUIRED IN ACCORDANCE WITH SECTION 150.04 OF THE GEORGIA SPECIFICATIONS. PLACEMENT OF PERMANENT PAVEMENT MARKINGS SHALL NOT BEGIN UNTIL FINAL SURFACE COURSE HAS BEEN COMPLETED FOR THIRTY (30) CALENDAR DAYS AND WILL BE COMPLETED WITHIN FORTY FIVE (45) CALENDAR DAYS AFTER THE FINAL SURFACE COURSE HAS BEEN COMPLETED. FAILURE TO PLACE PERMANENT PAVEMENT MARKINGS AS SPECIFIED WILL RESULT IN LIQUIDATED DAMAGES TO BE ASSESSED IN ACCORDANCE WITH SUBSECTION 108.08 OF THE SPECIFICATIONS.
20. PLACE PREFORMED PAVEMENT MARKINGS ON ALL CONCRETE BRIDGE DECKS IN ACCORDANCE TO THE DEPARTMENT'S SPECIFICATION SECTION 657. IT WILL BE REQUIRED TO REMOVE 90 PER CENT OF THE EXISTING DECK STRIPING PRIOR TO PLACEMENT OF PREFORMED PAVEMENT MARKINGS. PAYMENT OF THIS WORK SHALL BE INCLUDED IN THE OVERALL BID OF SECTION 657.
21. REHABILITATE THE EARTH SHOULDERS IN ACCORDANCE WITH DETAILS AND NOTES IN THE PLANS. THE FILLING SHALL INCLUDE GRADING, FURNISHING AND PLACEMENT OF BORROW MATERIAL. FILLING WORK SHALL BE PERFORMED AND PAID FOR IN ACCORDANCE WITH SECTION 210 OF THE SPECIFICATIONS EXCEPT AS NOTED IN DETAILS.
22. COMPLETE PHASE ONE (1) STAGED EARTH SHOULDER FILLING WORK FOR MILE LOG 0.000 TO MILE LOG 9.853 WITHIN THIRTY (30) CALENDAR DAYS, AFTER COMPLETION OF RESURFACING ROADWAY. COMPLETE PHASE TWO (2) EARTH SHOULDER FILLING WORK FOR MILE LOG 9.853 TO MILE LOG 22.541 WITHIN THIRTY (30) CALENDAR DAYS AFTER COMPLETION OF PHASE ONE (1) EARTH SHOULDER FILLING WORK FOR MILE 0.000 TO MILE 9.853. FAILURE TO COMPLETE EARTH SHOULDER FILLING WORK WITHIN THIS PHASED CONSTRUCTION TIME FRAME WILL RESULT IN LIQUIDATED DAMAGES ASSESSED IN ACCORDANCE WITH SUBSECTION 108.08 OF THE SPECIFICATIONS.
23. PROPERLY INSTALL EROSION CONTROL DEVICES AT ALL AREAS OF EARTH SHOULDER FILLING WORK. EROSION CONTROL SHALL BE PERFORMED AND PAID FOR IN ACCORDANCE WITH SECTION 161 OF THE SPECIFICATIONS.
24. GRASS ALL AREAS OF EARTH SHOULDER FILLING DAILY. GRASSING SHALL BE PERFORMED DAILY AND PAID FOR IN ACCORDANCE WITH SECTION 700 OF THE SPECIFICATIONS.
25. CONSTRUCT ELEVEN 11 TYPE D CURB CUT (WHEELCHAIR) RAMPS. LOCATIONS SHALL BE NOTED IN THE LOGS.