

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA**

**SPECIAL PROVISION**

**P. I. No. M004143  
COUNTY: COWETA/ MERIWETHER**

---

**Section 231—Miscellaneous Construction, Unpaved Roads and Streets**

---

*Add the following:*

---

**Section 231—Miscellaneous Construction, Roads, Streets, & Driveways**

---

**231.1 General Description**

This work consists of grading, excavating, removing and disposing of excavated material (gravel, asphalt, concrete, etc.), and compaction of subgrade. The work also includes all incidental work required to prepare an area so that the roads, streets and driveways can be surfaced to tie into the mainline of the resurfacing and/or widening projects, according to Project Details.

Perform items of work and furnish all items of material, equipment, and labor, including incidentals, required to complete this work to the satisfaction of the Engineer.

**231.1.01 Definitions**

General Provisions 101 through 150.

**231.1.02 Related References**

**A. Standard Specifications**

[Section 108—Prosecution and Progress](#)

[Section 205—Roadway Excavation](#)

[Section 400—Hot Mix Asphaltic Concrete Construction](#)

**B. Referenced Documents**

General Provisions 101 through 150.

**231.1.03 Submittals**

General Provisions 101 through 150.

**231.2 Materials**

Ensure that materials required in preparing the roads, streets, and driveways meet the applicable requirements of [Sections 205](#) of the Specifications. Bituminous prime is not required for this work.

**231.2.01 Delivery, Storage, and Handling**

General Provisions 101 through 150.