SUMMARY OF QUANTITIES- MISC QUANTITIES

REMOVE HIGHWAY SIGN SPECIAL ROADSIDE (EACH)

LOCATION (M. P.)	SIGN	DIRECTION	QUANTITY
24.40	R-SPEC 1	WB	1
23.00	R-SPEC 2	WB	1
20.03	R-SPEC 3	WB	1
19.17	R-SPEC 4	WB	1
13.75	R-SPEC 5	WB	1
12.55	R-SPEC 6	WB	1
11.42	R-SPEC 7	WB	1
9.92	R-SPEC 8	WB	1
9.82	R-SPEC 9	WB	1
9.23	R-SPEC 10	WB	1
8.00	R-SPEC 11	WB	1
5.83	R-SPEC 12	WB	1
5.00	R-SPEC 13	WB	1
3.70	R-SPEC 14	WB	1
3.46	R-SPEC 12	EB	1
4.29	R-SPEC 13	EB	1
7.80	R-SPEC 15	EB	1
8.20	R-SPEC 16	EB	1
8.66	R-SPEC 10	EB	1
10.02	R-SPEC 17	EB	1
10.67	R-SPEC 18	EB	1
12.00	R-SPEC 19	EB	1
17.40	R-SPEC 20	EB	1
18.37	R-SPEC 21	EB	1
19.67	R-SPEC 22	EB	1
22.56	R-SPEC 23	EB	1
22.80	R-SPEC 24	EB	1
23.48	R-SPEC 25	EB	1
24.60	R-SPEC 26	EB	1
TOTALS			29

REMOVE STRUCTURAL SUPPORT (EACH)

LOCATION (M. P.)	TYPE	DIRECTION	QUANTITY
24.87	VII	EB	1
25.36	II	EB	1
25.78	II	EB	1
27.34	VII	WB	1
26.79	II	WB	1
26.37	II	WB	1
25.28	II	WB	1
24.63	II	WB	1
24.22	II	WB	1
TOTALS			9

REMOVE GUARDRAIL (FEET)

LOCATION (M. P.)	DIRECTION	QUANTITY
24.90	EB	175
25.36	EB	124
25.78	EB	127
27.34	WB	175
25.28	WB	161
24.63	WB	164
TOTALS		926

NOTE: ALL EXISTING GUARDRAIL TO BE REMOVED IS LOCATED IN THE OUTSIDE SHOULDER OF ROADWAY.

REMOVE GUARDRAIL ANCHOR, ALL TYPES (EACH)

LOCATION (M. P.)	DIRECTION	QUANTITY
24.90	EB	2
25.36	EB	2
25.78	EB	2
27.34	WB	2
25.28	WB	2
24.63	WB	2
TOTALS		12

NOTE: ALL EXISTING GUARDRAIL ANCHORS TO BE REMOVED ARE LOCATED IN THE OUTSIDE SHOULDER OF ROADWAY.

MILE MARKERS (EACH)

REMOVE
54

NOTE: ALL EXISTING MILE MAKERS ARE TO BE REMOVED WITHIN THE PROJECT LIMITS. REMOVAL OF MILE MARKERS SHALL BE PAID FOR UNDER GRADING COMPLETE.

MISCELLANEOUS ROADWAY ITEMS

ITEM	UNIT	QUANTITY
GRADING COMPLETE - M004185	LS	LUMP

TRAFFIC CONTROL ITEMS

ITEM	UNIT	QUANTITY
TRAFFIC CONTROL - M004185	LS	LUMP
TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR	EA	9
TEMPORARY BARRIER, METHOD I	LF	2025
CHANGEABLE MESSAGE SIGNS, PORTABLE, TYPE 3	EA	4

EROSION CONTROL ITEMS

ITEM	UNIT	QUANTITY
AGRICULTURAL LIME	TN	1.13
LIQUID LIME	GL	0.94
FERTILIZER NITROGEN CONTENT	LB	18.75
FERTILIZER MIXED GRADE	TN	0.23
PERMANENT GRASSING	AC	0.25
MULCH	TN	0.75
WOOD FIBER BLANKET, TP II, SHOULDERS	SY	1460.00