8/8/2012 10:29:30 AM \\GDOT-DSN1\GOPLOT\OCE\OGC.cef alune M:\M004201\M004201_PRE\006-008-06Qty Ovhd Sign Summary_FFPR.prf

SUMMARY OF QUANTITIES - OVERHEAD HIGHWAY SIGNS

VOID

STATION	I-20 & I-285 TO	GUARD RAIL GA. STDS. 4010 & 4011A	GUARD RAIL ANCHORAGES GA. STDS. 4012C & 4050A,B,C				STRUCTURAL SUPPORT (LUMP)			HIGHWAY SIGNS, ALUMINUM PANELS (SQUARE FEET)				HIGHWAY SIGNS, ALUMINUM PANELS - INCL BRACKETS (SQUARE FEET)			
		LINEAR FEET	TYPE (EACH) I	II			SUPPORT NO.	TYPE	SPAN	SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL	SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL
I-285 NB																	
39.60	55						H396	EXISTING TYPE I		SPEC# 172	9' 6" X 2' 6"	23.75					
										SPEC# 172	20' 6" X 14' 0"	287.00					
										SPEC# 173	13' 0" X 2' 6"	32.50					
										SPEC# 173	13' 0" X 14' 0"	182.00					
										SPEC# 174	9' 6" X 2' 6"	23.75					
										SPEC# 174	20' 0" X 14' 0"	280.00	829.00				
39.50	56						H395	EXISTING TYPE VII		R554-6	EXISTING						
										SPEC# 145	26' 6" X 10' 0"	265.00	265.00				
38.90	57						H389	EXISTING TYPE I		SPEC# 175	9' 6" X 2' 6"	23.75					
										SPEC# 175	19' 0" X 15' 0"	285.00					
										SPEC# 148	11' 6" X 2' 6"	28.75					
										SPEC# 148	13' 0" X 15' 0"	195.00					
										SPEC# 150	11' 6" X 2' 6"	28.75					
										SPEC# 150	15' 0" X 15' 0"	225.00	786.25				
38.80	58						H388	EXISTING TYPE I		SPEC# 176	9' 6" X 2' 6"	23.75					
										SPEC# 176	19' 0" X 15' 6"	294.50					
										SPEC# 177	11' 6" X 2' 6"	28.75					
										SPEC# 177	13' 0" X 15' 6"	201.50					
										SPEC# 178	11' 6" X 2' 6"	28.75					
										SPEC# 178	15' 0" X 15' 6"	232.50	809.75				
38.50	59						H385	TYPE I	106'-0"	SPEC# 166	19' 0" X 13' 0"	247.00					
										SPEC# 151	11' 6" X 2' 6"	28.75					
										SPEC# 151	16' 6" X 13' 0"	214.50	490.25				
38.40	60						H384	TYPE I	91'-0"	SPEC# 179	9' 6" X 2' 6"	23.75					
										SPEC# 179	23' 0" X 12' 0"	276.00	299.75				
37.80	61						H378	TYPE I	87'-0"	SPEC# 136	9' 6" X 2' 6"	23.75					
										SPEC# 136	16' 6" X 14' 0"	231.00	254.75				
37.30	62						H373	TYPE I	72'-0"	SPEC# 138	9' 6" X 2' 6"	23.75					
										SPEC# 138	16' 6" X 14' 0"	231.00	254.75				
36.80	63						H368	TYPE I	82'-9"	SPEC# 142	9' 6" X 2' 6"	23.75					
										SPEC# 142	20' 6" X 12' 0"	246.00	269.75				
36.10	64						H361	TYPE VII		SPEC# 180	9' 6" X 2' 6"	23.75					
										SPEC# 180	18' 0" X 15' 0"	270.00					
										SPEC# 181	9' 6" X 2' 6"	23.75					
										SPEC# 181	16' 0" X 15' 0"	240.00	557.50				
SUBTOTAL #6													4816.75				

GEORGIA
DEPARTMENT OF TRANSPORTATION

DATE	REVISIONS

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES
OVERHEAD HIGHWAY SIGNS
NUMBER 6-008

8/8/2012 10:29:30 AM \\GDOT-DSN1\GOPLOT\OCE\OGC.cef alune M:\M004201\M004201_PRE\006-008-06Qty Ovhd Sign Summary_FFPR.prf