STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	M004202	11	135

SUMMARY OF QUANTITIES - OVERHEAD HIGHWAY SIGNS

	STATION (M.P.)	I-285 ZONE	GUARD RAIL GA. STDS. 4010 & 4011A LINEAR FEET	GUARD RAIL ANCHORAGES GA. STDS. 4012C & 4050A,B,C TYPE (EACH) I	II	STRUCTURAL SUPPORT (LUMP) SUPPORT NO.	TYPE	SPAN	HIGHWAY SIGNS, ALUMINUM PANELS (SQUARE FEET) SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL	HIGHWAY SIGNS, ALUMINUM PANELS - INCL BRACKETS (SQUARE FEET) SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL
	I-285 WB CONT'D															
**	~~27.00~~	~~40~~				~~H270~~	~~TYPE IV~~	~~120' 0''~~	~~SPEC# 185~~	~~16' 0'' X 13' 0''~~	~~208.00~~					
									~~SPEC# 186~~	~~53' 6'' X 19' 0''~~	~~1016.50~~					
									~~SPEC# 163~~	~~9' 6'' X 2' 6''~~	~~23.75~~					
									~~SPEC# 163~~	~~20' 0'' X 19' 0''~~	~~380.00~~	~~1628.25~~				
**	~~26.80~~	~~41~~				~~H268~~	~~TYPE I~~	~~107' 0''~~	~~SPEC# 187~~	~~9' 6'' X 2' 6''~~	~~23.75~~					
									~~SPEC# 187~~	~~80' 0'' X 20' 0''~~	~~1600.00~~	~~1623.75~~				
	26.40	42				H264	TYPE VII	23'-0''	R554-6							
									SPEC# 161	9' 6'' X 2' 6''	23.75					
									SPEC# 161	23' 0'' X 14' 0''	322.00	345.75				
**	~~25.70~~	~~43~~				~~H257~~	~~TYPE I~~	~~98' 0''~~	~~SPEC# 160~~	~~9' 6'' X 2' 6''~~	~~23.75~~					
									SPEC# 160	22' 0'' X 15' 0''	330.00	353.75				
**	~~25.30~~	~~44~~				~~H253~~	~~TYPE I~~	~~109' 6''~~	~~SPEC# 188~~	~~9' 6'' X 2' 6''~~	~~23.75~~					
									~~SPEC# 188~~	~~22' 0'' X 15' 0''~~	~~330.00~~	~~353.75~~				
**	~~24.50~~	~~45~~				~~H245~~	~~TYPE I~~	~~85' 0''~~	~~SPEC# 159~~	~~9' 6'' X 2' 6''~~	~~23.75~~					
									~~SPEC# 159~~	~~19' 0'' X 7' 0''~~	~~133.00~~	~~156.75~~				
	24.10	46				H241	TYPE I	85'-0''	SPEC# 128	9' 6'' X 2' 6''	23.75					
									SPEC# 128	19' 0'' X 7' 0''	133.00	156.75				
	23.70	47				H237	TYPE I	99'-0''	SPEC# 129	9' 6'' X 2' 6''	23.75					
									SPEC# 129	18' 6'' X 8' 0''	148.00	171.75				
	23.00	48				H230	TYPE VII	26'-6''	R554-6	EXISTING						
									SPEC# 124	9' 6'' X 2' 6''	23.75					
									SPEC# 124	26' 6'' X 13' 0''	344.50	368.25				
	22.80	49				H228	EXISTING TYPE III		SPEC# 158	20' 0'' X 8' 6''	170.00	170.00				
	22.70	50				H227	TYPE I	86'-0''	SPEC# 157	9' 6'' X 2' 6''	23.75					
									SPEC# 157	26' 6'' X 13' 0''	344.50	368.25				
	22.20	51				H222	TYPE I	98'-0''	SPEC# 156	9' 6'' X 2' 6''	23.75					
									SPEC# 156	26' 6'' X 14' 0''	371.00	394.75				
	22.00	52				H220	TYPE I	90'-0''	SPEC# 189	9' 6'' X 2' 6''	23.75					
									SPEC# 189	49' 6'' X 22' 0''	1089.00	1112.75				
	21.20	53				H212	TYPE I	97'-0''	SPEC# 117	9' 6'' X 2' 6''	23.75					
									SPEC# 117	66' 6'' X 20' 0''	1330.00	1353.75				
	20.70	54				H207	TYPE I	97'-0''	SPEC# 154	9' 6'' X 2' 6''	23.75					
									SPEC# 154	66' 6'' X 20' 0''	1330.00	1353.75				
	20.50	55				H205	TYPE I	97'-0''	SPEC# 155	19' 6'' X 14' 0''	273.00	273.00				
	20.30	56				H203	TYPE I	97'-0''	SPEC# 154	9' 6'' X 2' 6''	23.75					
									SPEC# 154	66' 6'' X 20' 0''	1330.00	1353.75				
**	SUBTOTAL #4											7422.50				

USE ON CONSTRUCTION

GEORGIA
DEPARTMENT OF TRANSPORTATION

DATE	REVISIONS
9/10/2013	H270, H268 REVISED
2/7/14	H270 AND H268 REVISED
10/30/14	**REMOVED STRUCTURES AND CHANGED QUANTITY

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

OVERHEAD HIGHWAY SIGNS

NUMBER 6-005