4/1/2014 12:34:19 PM \\GDOT-DSN1\GOPLOT\OCF\OGC.ocf tfambro M:\M004204\PRF\M004204_0009.prf

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	M004204	9	116

SUMMARY OF QUANTITIES - OVERHEAD HIGHWAY SIGNS

STATION	I-285 TO	GUARD RAIL GA. STDS. 4010 & 4011A	GUARD RAIL ANCHORAGES GA. STDS. 4012C & 4050A,B,C				STRUCTURAL SUPPORT (LUMP)			HIGHWAY SIGNS, ALUMINUM PANELS (SQUARE FEET)				HIGHWAY SIGNS, ALUMINUM PANELS - INCL BRACKETS (SQUARE FEET)			
		LINEAR FEET	TYPE (EACH) I	II			SUPPORT NO.	TYPE	SPAN	SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL	SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL
I-285 WB CONT'D																	
51.90	13						GH519	EXISTING TYPE I		SPEC# 114	20' 6'' X 14' 0''	287.00					
										SPEC# 114	9' 6'' X 2' 6''	23.75					
										SPEC# 115	19' 6'' X 14' 0''	273.00					
										SPEC# 115	9' 6'' X 2' 6''	23.75	607.50				
52.40	14						G524	EXISTING TYPE I		SPEC# 116	24' 6'' X 12' 0''	294.00					
										SPEC# 116	9' 6'' X 2' 6''	23.75	317.75				
53.80	15						G538	TYPE III	20'-6''	SPEC# 117	20' 6'' X 14' 0''	287.00					
										SPEC# 117	9' 6'' X 2' 6''	23.75	310.75				
54.30	16						G543	EXISTING TYPE I		R554-6	EXISTING						
										SPEC# 118	13' 6'' X 15' 0''	202.50					
										SPEC# 118	9' 6'' X 2' 6''	23.75					
										SPEC# 119	20' 6'' X 15' 0''	307.50					
										SPEC# 119	9' 6'' X 2' 6''	23.75	557.50				
54.90	17						G549	TYPE I	96'-0''	SPEC# 120	24' 6'' X 12' 0''	294.00					
										SPEC# 120	9' 6'' X 2' 6''	23.75	317.75				
*** 55.00	18						G550	TYPE III	90'-0"	SPEC# 121	25' 0'' X 14' 0''	350.00	350.00				
*** 55.50	19						G555	TYPE I	90'-0''	SPEC# 122	45' 0'' X 19' 0''	855.00					
										SPEC# 122	9' 6'' X 2' 6''	23.75	878.75				
55.80	20						G558	TYPE III	25'-0''	SPEC# 123	25' 0'' X 14' 0''	350.00	350.00				
56.00	21						G560	TYPE I	72'-0''	SPEC# 124	45' 0'' X 19' 0''	855.00					
										SPEC# 124	9' 6'' X 2' 6''	23.75	878.75				
56.10	22						G561	TYPE I	84'-0''	SPEC# 125	57' 0'' X 19' 0''	1083.00					
										SPEC# 125	9' 6'' X 2' 6''	23.75	1106.75				
58.90	23						G589	TYPE I	96'-0''	SPEC# 126	18' 6'' X 15' 0''	277.50					
										SPEC# 126	9' 6'' X 2' 6''	23.75					
										SPEC# 127	15' 0'' X 15' 0''	225.00					
										SPEC# 127	9' 6'' X 2' 6''	23.75	550.00				
59.40	24						G594	EXISTING TYPE I		SPEC# 128	18' 6'' X 15' 0''	277.50					
										SPEC# 128	9' 6'' X 2' 6''	23.75					
										SPEC# 129	15' 0'' X 15' 0''	225.00					
										SPEC# 129	9' 6'' X 2' 6''	23.75	550.00				
59.90	25						G599	TYPE I	110'-0''	SPEC# 130	18' 6'' X 15' 0''	277.50					
										SPEC# 130	9' 6'' X 2' 6''	23.75					
										SPEC# 131	18' 6'' X 15' 0''	277.50					
										SPEC# 131	9' 6'' X 2' 6''	23.75	602.50				
*** SUBTOTAL #2													7378.00				

USE ON CONSTRUCTION

GEORGIA
DEPARTMENT OF TRANSPORTATION

DATE	REVISIONS
9/25/13	TOTAL WAS 4844
1/10/14	TOTAL WAS 6670
3/28/14	***TOTAL WAS 6977

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

OVERHEAD HIGHWAY SIGNS

NUMBER 6-003

4/1/2014 12:34:19 PM \\GDOT-DSN1\GOPLOT\OCF\OGC.ocf tfambro M:\M004204\PRF\M004204_0009.prf