SUMMARY OF QUANTITIES

USE ON CONSTRUCTION

SURFACING QUANTITIES

ITEMS	UNITS	I-75	INSIDE SHOULDER	OUTSIDE SHOULDER	PAVING UNDER GUARDRAIL	TEMPORARY PAVEMENT FOR STAGING	PAVEMENT FOR PIPE REPLACMENT	SLEEPER SLABS	TOTALS
PLAIN PC CONC PVMT, CL HES CONC, 9 INCH THK	SY						270		270
PLAIN PC CONC PVMT, CL 1 CONC, 12 INCH THK	SY	123578							123578
RECYLCED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME, 165 LBS/SY	TON				2431	504			2935
RECYLCED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME, 220 LBS/SY	TON				3241	671		113	4025
RECYLCED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME, 330 LBS/SY	TON	20391							20391
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME, 330 LBS/SY	TON					1007			1007
ASPH CONC 12.5 MM SMA, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME, 135 LBS/SY	TON							85	85
GR AGGR BASE CRS, INCL MATL	TON	86485				2845	189		89519
BITUM TACK COAT	GAL				1473	610		103	2186
SAWED JOINTS IN EXIST PAVEMENTS - PCC	LF	43957							43957
CONCRETE V GUTTER	LF		5085						5085
MILL ASPH CONC PVMT, 3 1/2 IN DEPTH	SY							1023	1023
HIGH STRENGTH PVMT REINF FABRIC, 18 IN WIDTH	LF							92	92
ALTERNATE 1									
RECYLCED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL POLYMER-MODIFIED BITUM MATL & H LIME, 165 LBS/SY	TON		4030	4432					8462
RECYLCED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME, 220 LBS/SY	TON		5373	5909					11282
RECYLCED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME, 330 LBS/SY	TON		8059	8864					16923
GR AGGR BASE CRS, INCL MATL	TON		22786	25063					47849
BITUM TACK COAT	GAL		4884	5372					10256
ASPHALT-RUBBER JOINT AND CRACK SEAL, TP S	LF		43957	43957					87914
ALTERNATE 2									
ROLLER COMPACTED CONCRETE, 8.25 INCH	SY		48837	53718					102555
SEALING ROADWAY JOINTS AND CRACKS, TP A	LF		43957	43957					87914
GRIND CONC PVMT - 0.25"	SY		48837	53718					102555
GR AGGR BASE CRS, INCL MATL	TN		17090	18798					35888
ALTERNATE 3									
PLAIN PC CONC PVMT, CL 1 CONC, 8 INCH THK	SY		48837	53718					102555
GR AGGR BASE CRS, INCL MATL	TN		17090	18798					35888

INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)

TOTAL 18 GLM

FULL DEPTH SLAB REPLACEMENT

TOTAL 1095 CY

TO BE USED AS DIRECTED BY ENGINEER FOR THE REMOVAL AND REPLACEMENT OF DAMAGED SLABS IN LANE ONE.

PRICE ADJUSTMENT - UNLEADED FUEL

LUMP SUM M004205-CST

PRICE ADJUSTMENT - DIESEL FUEL

LUMP SUM M004205-CST

PRICE ADJUSTMENT - ASPHALT CEMENT

LUMP SUM M004205-CST

CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3

TOTAL 4 EACH

TO BE USED AS DIRECTED BY ENGINEER

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES
09-27-2010

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES
M004205-CST
DRAWING No. 6-01

3/1/2007 GQUANT