NON-FLARING TYPE 12 ANCHORS CAN BE SUBSTITUTED FOR FLARED TYPE 12 ANCHORS AS DIRECTED BY THE ENGINEER.

GUARDRAIL QUANTITIES
GA STD. 4000W, 4010, 4011A, 4012C, 4012D, 4040, 4051, 4057, 4055, 4270 4940

ROADWAY	STATION RANGE OR LOCATION	SIDE	"W" BEAM GUARDRAIL		"T" BEAM GUARDRAIL		ANCHORAGE		
			SINGLE FACE	DOUBLE FACE	SINGLE FACE	DOUBLE FACE	TP 1	TP 12	TP 10-D
I-75	1000+00 TO 1098+44	MEDIAN		9844					1
I-75	1000+00	LEFT							1
I-75	1007+25 TO 1013+00	RIGHT	575				1	1	
I-75	1012+00 TO 1016+75	LEFT	475				1	1	
I-75	1050+25 TO 1057+00	RIGHT	675				1	1	
I-75	1054+50 TO 1062+75	LEFT	825				1	1	
I-75	1062+07 TO 1065+07	RIGHT	300					1	
I-75	1065+07 TO 1065+27.65	RIGHT			21				
I-75	1065+35 TO 1068+10	MEDIAN	275				1	1	
I-75	1065+93.35 TO 1066+14	LEFT			21				
I-75	1066+14 TO 1069+64	LEFT	350					1	
I-75	1103+12 TO 1105+37	RIGHT	225					1	
I-75	1098+44 TO 1098+65	MED LT			21				
I-75	1098+44 TO 1098+65	MED RT			21				
I-75	1105+37 TO 1105+57.65	RIGHT			21				
I-75	1111+50.35 TO 1111+71	LEFT			21				
I-75	1111+71 TO 1114+71	LEFT	300					1	
I-75	1120+75 TO 1120+96	MED LT			21				
I-75	1120+75 TO 1120+96	MED RT			21				
I-75	1120+96 TO 1226+22	MEDIAN		10526					
I-75	1137+00 TO 1139+00	RIGHT	200				1	1	
I-75	1144+00 TO 1145+00	RIGHT	100				1	1	
I-75	1160+25 TO 1167+00	RIGHT	675				1	1	
I-75	1163+50 TO 1168+75	LEFT	525				1	1	
I-75	1171+25 TO 1179+50	RIGHT	825				1	1	
I-75	1178+00 TO 1191+25	LEFT	1325				1	1	
I-75	1182+25 TO 1189+00	RIGHT	675				1	1	
I-75	1218+25 TO 1222+50	LEFT	425				1	1	
TOTALS			8750	20370	168		13	17	2

BRIDGE CULVERT - QUADRUPLE 10 X 8 - STRUCTURE NO. F-91 - TO BE EXTENDED
SPECIAL DESIGN BOX CULVERT - GEORGIA STANDARDS 2327 & 2332

STATION 1178+91 LEFT (I-75) SKEW = 90 DEG. HEIGHT OF FILL = 5.00 FT

ITEM	UNIT	BARREL	WINGWALL & PARAPET	APRON	TOTAL
CLASS A CONCRETE	CY	26	23		49
BAR REINFORCING STEEL	LB	3090	1357		4447
FOUNDATION BACKFILL MATERIAL, TYPE II	CY	11			11

BRIDGE CULVERT - QUADRUPLE 10 X 8 - STRUCTURE NO. F-92 - TO BE EXTENDED
SPECIAL DESIGN BOX CULVERT - GEORGIA STANDARDS 2327 & 2332

STATION 1177+47 RIGHT (I-75) SKEW = 90 DEG. HEIGHT OF FILL = 5.00 FT

ITEM	UNIT	BARREL	WINGWALL & PARAPET	APRON	TOTAL
CLASS A CONCRETE	CY	34	23	17	74
BAR REINFORCING STEEL	LB	4120	1357	1206	6683
FOUNDATION BACKFILL MATERIAL, TYPE II	CY	14			14

SUMMARY OF QUANTITIES

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES
05-21-2010

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES

M004205-CST

DRAWING No. 6-03

STATE GA | PROJECT NUMBER M004205-CST | SHEET NO. 16 | TOTAL SHEETS 302

6/10/2010 10:21:16 AM \\GDOT-DSN\GDPLOT\OCF\GO_Kip8000.qcf jotaylor M:\M003340 - Sta. 1000+00 to Sta. 1226+22\DGN\PRF\006-003_M003340DN01.prf 6/10/2010 10:21:16 AM \\GDOT-DSN\GDPLOT\OCF\GO_Kip8000.qcf jotaylor M:\M003340 - Sta. 1000+00 to Sta. 1226+22\DGN\PRF\006-003_M003340DN01.prf 6-03