INDEX

DRAWING NO.	SHEET NO.	DESCRIPTION
1-01	1	COVER
2-01	2	INDEX AND GENERAL NOTES
3-01	3	REVISION SUMMARY
6-01	4	SUMMARY OF QUANTITIES
7-01	5	QUANTITIES REQUIRED BY AMENDMENT SHEET
8-01	6	QUANTITIES REQUIRED ON CONSTRUCTION SHEET
9-01	7	DETAILED ESTIMATE
35-01 TO 35-08	8-15	BRIDGE NO. - 1 PLANS
35-09 TO 35-13	16-21	BRIDGE NO. - 2 PLANS
35-15 TO 35-21	22-28	BRIDGE NO. - 3 PLANS
		GDOT CONSTRUCTION STANDARDS
		GA STD 3901 - BAR BENDING DETAILS (8/69)
		GA STD 4010 - "W" BEAM GUARDRAIL (5/99)
		GA STD 4011A - POST AND OFFSET BLOCKS FOR "W" AND "T" BEAM GUARDRAIL (REPLACES STANDARDS 4011 & 4271) -
		ADDED COMPOSITE BLOCK (12/01)
		GA STD 4012C - GUARDRAIL CONNECTION AT BRIDGE END OR AT CONCRETE BARRIER END (3/05)
		GA STD 4012D - GUARDRAIL ANCHORAGE TYPE 1 (7/02)
		GA STD 4270 - "T" BEAM GUARDRAIL (11/99)
		GA STD 9017J - CONCRETE SPILLWAYS (ADJACENT TO APPROACH SLABS) (2/95)
		GA STD 9017R - REINFORCED CONCRETE APPROACH SLAB WITH ASPHALT INLAY, 30 FT. LENGTH (9/02)
		GA STD 9102 - TRAFFIC CONTROL DETAIL FOR LANE CLOSURE ON TWO-LANE HIGHWAY (3/06)

GENERAL NOTES

1. GEORGIA811 Utilities Protection Center, Inc. Know what's below. Call before you dig.

2. ANY SIGN THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED PER GA. STANDARDS. NO SEPARATE PAYMENT WILL BE MADE FOR RESETTING OR REPLACING. COST TO BE INCLUDED IN OVERALL BID.

3. NOTICE OF INTENT IS NOT REQUIRED.

4. ALL WORK SHALL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL AND PROPERLY DISPOSING OF ALL UNSALVAGEABLE MATERIAL IN THIS PROJECT. THE CONTRACTOR SHALL NOT DEPOSIT ANY MATERIAL IN ANY WATERWAY. DISPOSAL SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.