VOID



# SUMMARY OF QUANTITIES-OVERHEAD HIGHWAY SIGNS

| MILEPOST | INSTL NO | GUARDRAIL GA.STDS.4010 & 4011A | GUARD RAIL ANCHORAGES GA. STDS. 4012C & 4050 A,B,C | | STRUCTURAL SUPPORT OVHD(LUMP SUM) | | | HIGHWAY SIGNS, ALUMINUM EXTRUDED PANELS REFLECTIVE SHEETING TYPE 3 (SQUARE FEET) | | | | HIGHWAY SIGNS, ALUMINUM EXTRUDED PANELS REFLECTIVE SHEETING TYPE 3 (SQUARE FEET) | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | TYPE (EACH) | | | | | | | | | | | | |
| | | LINEAR FEET | | | SUPPORT NO. | TYPE | SPAN | SIGN NO. | SIGN SIZE | SUB-TOTAL | TOTAL | SIGN NO. | SIGN SIZE | SUB-TOTAL | TOTAL |
| I-75 NB | | | | | | | | | | | | | | | |
| 227.50 | 1 | | | | C2275 | III | 17'-0" | SPEC #100 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #100 | 17'-0" X 14'-0" | 238.00 | 265.50 | | | | |
| 228.00 | 2 | | | | C2280 | I | NEW | SPEC #101 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #101 | 21'-6" X 12'-0" | 258.00 | 285.50 | | | | |
| 229.80 | 3 | | | | C2298 | VII | N/A | SPEC #102 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #102 | 18'-6" X 7'-0" | 129.50 | 157.00 | | | | |
| 230.80 | 4 | | | | C2308 | I | 96'-0" | SPEC #103 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #103 | 16'-6" X 8'-0" | 132.00 | 159.50 | | | | |
| 233.40 | 5 | | | | C2334 | I | NEW | SPEC #104 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #104 | 20'-0" X 11"-0" | 220.00 | 247.50 | | | | |
| 233.90 | 6 | | | | C2339 | I | NEW | SPEC #105 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #105 | 20'-0" X 11"-0" | 220.00 | 247.50 | | | | |
| 234.40 | 7 | | | | C2344 | I | NEW | SPEC #106 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #106 | 18'-0" X 12'-0" | 216.00 | 243.50 | | | | |
| 235.70 | 8 | | | | C2357 | I | 19'-6" | SPEC #107 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #107 | 19'-6" X 17'-0" | 331.50 | 359.00 | | | | |
| 236.20 | 9 | | | | C2362 | I | 101'-0" | SPEC #108 | 15'-6" X 2'-6" | 38.75 | | | | | |
| | | | | | | | | SPEC #108 | 17'-0" X 15'-0" | 255.00 | | | | | |
| | | | | | | | | SPEC #109 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #109 | 19'-6" X 16'-0" | 312.00 | 633.25 | | | | |
| 236.70 | 10 | | | | C2367 | I | 104'-0" | SPEC #110 | 14'-0" X 15'-0" | 210.00 | | | | | |
| | | | | | | | | SPEC #111 | 15'-6" X 2'-6" | 38.75 | | | | | |
| | | | | | | | | SPEC #111 | 17'-0" X 15'-0" | 255.00 | | | | | |
| | | | | | | | | SPEC #112 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #112 | 21'-0" X 14'-0" | 294.00 | 825.25 | | | | |
| 237.50 | 11 | | | | C2375 | I | 80'-0" | SPEC #113 | 13'-0" X 2'-6" | 32.50 | | | | | |
| | | | | | | | | SPEC #113 | 20'-0" X 16'-0" | 320.00 | | | | | |
| | | | | | | | | SPEC #114 | 13'-0" X 2'-6" | 32.50 | | | | | |
| | | | | | | | | SPEC #114 | 15'-6" X 16'-0" | 248.00 | 633.00 | | | | |
| 238.20 | 12 | | | | C2382 | I | 112'-0" | SPEC #115 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #115 | 25'-0" X 17'-0" | 425.00 | | | | | |
| | | | | | | | | SPEC #116 | 13'-0" X 2'-6" | 32.50 | | | | | |
| | | | | | | | | SPEC #116 | 20'-6" X 16'-0" | 328.00 | 813.00 | | | | |
| 238.80 | 13 | | | | C2388 | VII | N/A | SPEC #118 | 11'-0" X 2'-6" | 27.50 | | | | | |
| | | | | | | | | SPEC #118 | 25'-0" X 18'-0" | 450.00 | 477.50 | | | | |
| SUB-TOTAL 1 | | | | | | | | | | 5347.00 | | | | | |

GRESHAM SMITH AND PARTNERS

URS

**GEORGIA**
**DEPARTMENT OF TRANSPORTATION**

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
**SUMMARY QUANTITIES**

DRAWING No. 06-001

3/1/2007 GPLN