SUMMARY OF QUANTITIES - MISC QUANTITIES

VOID

INSTALL NEW HIGHWAY OVERHEAD SIGN STRUCTURES (EACH)					
LOCATION (MILE POST)	DIRECTION	SIGN	QUANTITY		REMOVE EXISTING STRUCTURE
			TYPE I	TYPE III	
85.70	NB	SPEC #101	1		1
85.80	NB	SPEC #102	1		1
86.70	NB	SPEC #104		1	1
88.20	NB	SPEC #107	1		1
88.70	NB	SPEC #110	1		1
89.90	NB	SPEC #112	1		1
90.30	NB	SPEC #113	1		1
91.40	NB	SPEC #114	1		1
91.70	NB	SPEC #115	1		1
92.70	NB	SPEC #116	1		1
94.00	NB	SPEC #120	1		1
95.10	NB	SPEC #126	1		1
95.30	NB	SPEC #127	1		1
96.20	SB	SPEC #139	1		1
93.30	SB	SPEC #146	1		1
91.70	SB	SPEC #147	1		1
90.10	SB	SPEC #150	1		1
89.50	SB	SPEC #151	1		1
87.30	SB	SPEC #160	1		1
85.80	SB	SPEC #103	1		1
	TOTAL		19	1	20

REMOVE HIGHWAY SIGN SPECIAL ROADSIDE (EACH)			
LOCATION (MILE POST)	SIGN	DIRECTION	QUANTITY
88.65	R-SPEC #1	NB	1
89.60	R-SPEC #1	SB	1
92.90	R-SPEC #2	NB	1
94.08	R-SPEC #2	SB	1
TOTAL			4

EROSION CONTROL ITEMS		
ITEM	UNIT	QUANTITY
AGRICULTURAL LIME	TN	1
FERTILIZER NITROGENCONTENT	LB	10
FERTILIZER MIXED GRADE	TN	1
TEMPORARY GRASSING	AC	1
PERMANENT GRASSING	AC	1
MULCH	TN	1
WOOD FIBER BLANKET, TP II, SHOULDERS	SY	10
CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM	LF	300
MAINT. OF SEDIMENT BARRIER-BALED STRAW	LF	150

MISCELLANEOUS ROADWAY ITEMS		
ITEM	UNIT	QUANTITY
GRADING COMPLETE-M004427	LS	LUMP
GUARDRAIL (AS DIRECTED BY ENGINEER)	LF	600
GUARDRAIL ANCHORAGE, TP 1 (AS DIRECTED BY ENGINEER)	EA	2
GUARDRAIL ANCHORAGE, TP 12 (AS DIRECTED BY ENGINEER)	EA	2
CONCRETE BARRIER, TYPE 26S (AS DIRECTED BY ENGINEER)	LF	500
CONCRETE BARRIER, TYPE 26 (AS DIRECTED BY ENGINEER)	LF	100

TRAFFIC CONTROL ITEMS		
ITEM	UNIT	QUANTITY
TRAFFIC CONTROL-M004427	LS	LUMP
TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR	EA	5
TEMPORARY BARRIER, METHOD I	LF	1000
CHANGEABLE MESSAGE SIGNS, PORTABLE, TYPE 3	EA	4