



						STATE GA		P. I. NUMBER M004569		SHEET NO. 2		TOTAL SHEETS 16	
	INDEX												
	SHEET NO.	DRAWING NO.	DESCRIPTION										
	1	1-001	COVER										
	2	2-001	INDEX AND GENERAL NOTES										
	3	3-001	REVISION SUMMARY										
	4	6-001	SUMMARY OF QUANTITIES										
	5	7-001	QUANTITIES REQUIRED BY AMENDMENT SHEET										
	6	8-001	QUANTITIES REQUIRED ON CONSTRUCTION SHEET										
	7-12	35-01 TO 35-06	CULVERT PLANS										
			GDOT CONSTRUCTION STANDARDS										
	13	GA STD 2310	REINFORCED CONC. BOX CULVERT DOUBLE 10'X4' TO TRIPLE 10'X12' (JULY 1955)										
	14	GA STD 2318	DETAILS FOR EXTEND CONCRETE BOX CULVERTS WITH SKEWS BELOW 75° (JUNE 1955)										
	15	GA STD 9102	TRAFFIC CONTROL DETAIL FOR LANE CLOSURE ON TWO-LANE DIVIDED HIGHWAY										
			GDOT CONSTRUCTION DETAILS										
	16	D-4I	CONSTRUCTION EXIT										
	16		TOTAL SHEETS										
ENVIRONMENTAL RESOURCES IMPACT TABLE													
RESOURCE NAME/TYPE	LOCATION		SIDE	CONSTRUCTION ACTIVITY	PERMITTED ACTIVITY	CONTROLLING CRITERIA	SPECIAL PROVISION	COMMENTS INCLUDING ANY PERMIT EXPIRATION DATES					
	BEGINNING STA.	ENDING STA.											
PERENNIAL STREAM PSI	FROM 10+00± TO 9+86±	FROM 10+93± TO 11+07±	LEFT & RIGHT	SCOUR REPAIR AND DEBRIS REMOVAL	28 LINEAR FEET (.004 ACRE) PERMANENT IMPACT DUE TO FILL	NW3a PERMIT	N/A	THE CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION RELATED ACTIVITIES (EASEMENTS, STAGING, VEHICULAR USE, BORROW OF WASTE ACTIVITIES, CONSTRUCTION, TRAILER PLACEMENT AND STAGING) BE RESTRICTED TO THE PROPOSED CULVERT REHABILITATION ON US80/SR22 OVER CULPEPPER CREEK RIGHT-OF-WAY.					
PS1 BUFFER	FROM 10+00± TO 9+86±	FROM 10+93± TO 11+07±	LEFT & RIGHT	SCOUR REPAIR AND DEBRIS REMOVAL	<0.01 ACRE	NPDES	N/A	ALL BUFFER IMPACTS ARE EXEMPT UNDER THE "ROADWAY DRAINAGE EXEMPTION"					
INVASIVE SPECIES DENSE INFESTATION	N/A	N/A	RIGHT	NONE	N/A	N/A	N/A	0.15 ACRE DENSE INFESTATION OF CHINESE PRIVET AND JAPANESE HONEYSUCKLE TO NORTHWEST OF PROJECT. SPECIES AND SITE SPECIFIC APPROPRIATE MEASURES TO BE USED AS DESCRIBED IN GEORGIA STANDARD SPECIFICATIONS SECTION 201, CLEARING AND GRUBBING OF RIGHT-OF-WAY.					
PERENNIAL STREAM PS2	OUTSIDE THE PROJECT AREA	OUTSIDE THE PROJECT AREA		NONE	NONE	N/A	N/A						
PS2 BUFFER	OUTSIDE THE PROJECT AREA	OUTSIDE THE PROJECT AREA		NONE	NONE	NPDES	N/A						
					 SASTRY & ASSOCIATES, INC. 11030 JONES BRIDGE ROAD, SUITE 201 ALPHARETTA, GA 30022 PHONE: 678-366-9375 FAX: 770-442-0761		REVISION DATES		STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION				
							OFFICE: BRIDGES AND STRUCTURES						
							INDEX AND GENERAL NOTES						
						DRAWING No. 2-001							