

SHEET NO.	DWG NO.	DESCRIPTION
1	01-001	COVER SHEET
2	02-001	INDEX AND GENERAL NOTES
3	03-001	REVISION SUMMARY SHEET
4	05-001	STAGING TYPICAL SECTIONS
5-6	06-001 - 06-002	SUMMARY OF QUANTITIES
7	07-001	QUANTITIES REQUIRED BY AMENDMENT AND ON CONSTRUCTION
8-9	13-001 - 13-002	CONSTRUCTION PLANS
10-13	19-001 - 19-004	STAGING PLANS
14-15	26-001 - 26-002	SIGNING AND MARKING PLANS
16-26	35-001 - 35-011	BRIDGE REHABILITATION PLANS
CONSTRUCTION DETAILS		
27	40-001 P-3	RESEALING JOINTS IN PPC CONCRETE PAVEMENT & BRIDGE DECKS PATCHING PCC CONCRETE PAVEMENT 9-88
28	40-002 P-7	PAVEMENT EDGE TREATMENT ASPHALT AND CONCRETE PAVEMENT 11-11
29	40-003 S-9	CONTINUOUS INDENTATION RUMBLE STRIPS-GROUND-IN-PLACE INTERSTATE 3-10
30	40-004 T-11B	DETAILS OF PAVEMENT MARKING PLACEMENT LIMITED ACCESS ROADWAY 1-00
31	40-005 T-15B	DETAILS OF RAISED PAVEMENT MARKER LOCATION LIMITED ACCESS ROADWAY 1-00
32	40-006 T-15C	DETAILS OF RAISED PAVEMENT MARKERS 9-11
GEORGIA STANDARDS		
33	41-001 GA. STD. 3901	BAR BENDING DETAILS 8-69
34	41-002 GA. STD. 4013	GUARDRAIL ANCHORAGE TYPE 5 AND 6 - GUARDRAIL ATTACHMENT TO COLUMNS, PIERS, WALLS 6-98
35	41-003 GA. STD. 4960	TEMPORARY BARRIER (END TREATMENT OPTIONS) 5-07
36	41-004 GA. STD. 4961	DETAILS OF PRECAST TEMPORARY BARRIERS 9-06
37	41-005 GA. STD. 4962	TEMPORARY TRAFFIC IMPACT ATTENUATOR SAND LOADED MODULES 5-99
38	41-006 GA. STD. 9017M	STANDARD 30 FT. LENGTH REINFORCED CONCRETE APPROACH SLAB (WITH CONCRETE BARRIER) 6-93
39	41-007 GA. STD. 9100	TRAFFIC CONTROL GENERAL NOTES, STANDARD LEGEND, AND MISCELLANEOUS DETAILS 3-06
40	41-008 GA. STD. 9106	TRAFFIC CONTROL DETAIL FOR LANE CLOSURE ON MULTI-LANE DIVIDED HIGHWAY 9-07
40		TOTAL SHEETS

GENERAL NOTES

1. ALL SALVAGEABLE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR.
2. THERE IS NO SUITABLE PLACE TO BURY THE EXISTING BRIDGE/CONSTRUCTION DEBRIS WITHIN THE PROJECT'S LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF THE EXISTING BRIDGE/CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.
3. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL. SEE SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERETO FOR ADDITIONAL INFORMATION.
4. ALL WORK WILL BE COMPLETED WITHIN THE EXISTING RIGHT-OF-WAY.
5. IT SHALL BE THE REponsibility OF THE CONTRACTOR TO PREVENT ANY SEDIMENTATION WITHIN STATE WATERS. THE COST OF THIS SHALL BE INCLUDED IN THE OVERALL BID SUBMITTED.
6. THE REMOVAL OF EXISTING ASPHALT SHOULDER AND SUBBASE SHALL BE INCLUDED IN THE PRICE FOR PAY ITEM 210-0100 - GRADING COMPLETE.
7. CONTRACTOR SHALL LIMIT WORK TO ONE BRIDGE AT A TIME.

A NOTICE OF INTENT IS NOT REQUIRED FOR THIS PROJECT



Know what's below.
Call before you dig.

ENVIRONMENTAL RESOURCES IMPACT TABLE

RESOURCE NAME/TYPE	LOCATION		SIDE	CONSTRUCTION ACTIVITY	PERMITTED ACTIVITY	CONTROLLING CRITERIA	SPECIAL PROVISION	COMMENTS INCLUDING ANY PERMIT EXPIRATION DATES
	APPROX BEGIN STA	APPROX END STA						
MIGRATORY BIRDS	1686+63.01	1688+82.10	BOTH	REHABILITATION OF EXISTING BRIDGE	REFER TO SPECIAL PROVISION 107.23G	ENDANGERED SPECIES ACT	107.23G	THE OFFICE OF ENVIRONMENTAL SERVICES SHALL BE CONTACTED PRIOR TO INSTALLATION OF EXCLUSIONARY DEVICES. CONTRACTOR SHALL DIRECT QUESTIONS TO THE ENGINEER, AND THE ENGINEER SHALL CONTACT ENVIRONMENTAL SERVICES IF NECESSARY FOR RESOLUTION.



Heath & Lineback Engineers
INCORPORATED
2390 CANTON ROAD, BUILDING 200
MARIETTA, GEORGIA 30066-5393
(770)424-1668

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: BRIDGES AND STRUCTURES
INDEX AND GENERAL NOTES

1-75 OVER CEDAR CREEK ROAD

DRAWING No.
02-001