

PROJECT GENERAL NOTES

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE GEORGIA DEPARTMENT OF TRANSPORTATION STANDARD AND SUPPLEMENTAL SPECIFICATIONS, CURRENT EDITION.
2. ALL KNOWN UTILITY FACILITIES ARE SHOWN SCHEMATICALLY ON PLANS, AND ARE NOT NECESSARILY ACCURATE IN LOCATION AS TO PLAN OR ELEVATION. UTILITY FACILITIES SUCH AS SERVICE LINES OR UNKNOWN FACILITIES NOT SHOWN ON PLANS WILL NOT RELIEVE THE CONTRACTOR OF THEIR RESPONSIBILITY UNDER THIS REQUIREMENT. "EXISTING UTILITY FACILITIES" MEANS ANY UTILITY THAT EXISTS ON THE PROJECT IN ITS ORIGINAL, RELOCATED OR NEWLY INSTALLED POSITION.
3. THE FOLLOWING UTILITIES HAVE FACILITIES IN THE PROJECT AREA:

<ol style="list-style-type: none"> 1. Jonathan Todd, PE Eastern Division Engineer, Atlanta Gas Light Company 10 Peachtree Place, 11th Floor, Suite 1000, Atlanta, GA 30309 2. Tom Goodwin Distribution, AT&T Corporation 3841 Wrightsboro Road, Augusta, GA 30909 3. Steven Behrend, PE Design Engineer, Augusta Utilities Department Engineering Division 360 Bay Street, Suite 180, Augusta, GA 30901 4. Kevin O'Meara Construction Supervisor, Comcast Cable Communications, Inc. 105 River Shoals Parkway, Augusta, GA 30909 	<ol style="list-style-type: none"> 5. Kristi Griffin Distribution Engineer, Georgia Power 642 Woodland Rd, Waynesboro, GA 30830 6. Jonathan Ray Tower Cloud 9501 International Court North, Saint Petersburg, FL 33716 7. Gary McFerrin Field Engineer, WOW 3714 Wheeler Rd, Augusta, GA 30909
--	---
4. INGRESS AND EGRESS SHALL BE MAINTAINED AT ALL TIMES TO ADJACENT PROPERTIES. REFER TO SUB-SECTION 107.07 OF THE GEORGIA STANDARD SPECIFICATIONS.
5. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FURNISH SUITABLE BORROW MATERIAL FOR THE PROJECT AND DISPOSE OF ANY UNSUITABLE OR WASTE MATERIAL.
6. STRUCTURES, TREES, SHRUBS, AND OTHER PLANT MATERIAL THAT FALL WITHIN THE RIGHT-OF-WAY AND EASEMENT LIMITS, BUT OUTSIDE THE LIMITS OF CONSTRUCTION, SHALL NOT BE DISTURBED UNLESS DIRECTED BY THE ENGINEER.
7. THE CONTRACTOR SHALL OBSERVE ALL APPLICABLE LOCAL, STATE AND FEDERAL SAFETY REGULATIONS REGARDING PIPE INSTALLATION IN TRENCHES. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COST INCURRED TO COMPLY WITH THIS REQUIREMENT.
8. IN AREAS WHERE NEW PAVEMENT OR PAVEMENT WIDENING IS REQUIRED, SAW CUT OF EXISTING PAVEMENT WILL BE REQUIRED IN ACCORDANCE WITH SECTION 411 OF THE GEORGIA STANDARD SPECIFICATIONS AND WILL BE INCLUDED IN PRICE BID FOR "GRADING COMPLETE".
9. ALL ITEMS TO BE DEMOLISHED AS PART OF THE ROADWAY CONSTRUCTION ARE TO BE INCLUDED IN PRICE BID FOR "GRADING COMPLETE".
10. NO SEPARATE PAYMENT WILL BE MADE FOR PAVEMENT, GRADING OR ANY OTHER OPERATIONS REQUIRED FOR DETOUR CONSTRUCTION AND SHALL BE INCLUDED IN PRICE BID FOR "TRAFFIC CONTROL".
11. ALL CUT AND FILL SLOPES SHALL BE GRASSED IMMEDIATELY AFTER SLOPES ARE STABILIZED IN ORDER TO REDUCE EROSION. IF THE SEASON DOES NOT PERMIT GRASSING, STRAW MULCH SHALL BE USED AS DIRECTED BY THE ENGINEER.
12. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO OR CONCURRENT WITH LAND DISTURBANCE ACTIVITIES AND SHALL BE MAINTAINED AT ALL TIMES. ADDITIONAL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTION OR AS DIRECTED BY THE ENGINEER.
13. SPRINKLER SYSTEMS TO BE HANDLED AS FOLLOWS:

CASE 1 SYSTEMS WITHIN THE CONSTRUCTION LIMITS OWNED BY INDIVIDUALS OR PRIVATE COMPANIES ARE TO BE REMOVED TO THE BACK OF THE CONSTRUCTION LIMITS AND PLUGGED.	CASE 2 SYSTEMS SHOWN BY THE PLANS TO BE REMOVED AND RELOCATED SHALL BE RELOCATED TO THE BACK OF THE SIDEWALK. COST SHALL BE INCLUDED IN PRICE BID FOR "GRADING COMPLETE".
---	---
14. AN N.O.I. (NOTICE OF INTENT) IS NOT REQUIRED FOR THIS PROJECT. THE DISTURBED AREA IS 0.20 ACRES.

Environmental Resources Impact Table						
These resources and the restrictions listed are governed by state and federal law.						
Resource Name <small>(from Section A of the ECT)</small>	Location			Permitted Construction Activity <small>(from Section A of the ECT)</small>	Special Provision? <small>(from Section B of the ECT)</small>	Comments <small>(from Section C of the ECT, comments only)</small>
	Beginning STA	Ending STA	Side			
CSX Railroad	102+80.78	102+86.02	LT & RT	Re-striping of existing pavement markings	NA	The contractor shall ensure that no construction-related activities (such as the use of easements, staging, construction, vehicular use, borrow or waste activities, sediment basins, and trailer placement), other than those shown on the approved plans, occur within the boundary of this resource.
404 Permits and Variances (from Section D of the ECT)			Expiration dates (if applicable) Contact GDOT OES 6 months prior to expiration, if work will extend beyond this date.			
None						
If there are no resources, indicate "None" in the first row. Include this table in the General Notes section of the plans as always.						
ECT = Environmental Commitments Table, AKA "Green Sheet".						



CH2MHILL
 Embassy Row
 6600 Peachtree Dunwoody Road
 Building 400 - Suite 600
 Atlanta, GA 30328
 770-604-9095



REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

STEVENS CREEK RD AT
RIVER WATCH PKWY (SR 104)

DRAWING No.
04-01