SUMMARY OF QUANTITIES

VOID

ITS QUANTITIES

631-2343 LED PIXEL CMS NON-WALK-IN, 3 X 15, 18 IN, TYPE B	
UNIT	QUANTITY
EA	1

631-8000 TESTING - 0011692	
UNIT	QUANTITY
LS	LUMP

638-1003 STR SUPPORT FOR OVHD SIGN TP 3	
UNIT	QUANTITY
EA	1

639-4004 STRAIN POLE TP IV	
UNIT	QUANTITY
EA	10

647-2120 PULLBOX, PB-2	
UNIT	QUANTITY
EA	1

647-2141 PULLBOX, PB-4S	
UNIT	QUANTITY
EA	21

647-2170 PULLBOX, PB-7	
UNIT	QUANTITY
EA	7

682-6120 CONDUIT, RIGID, 2 IN	
UNIT	QUANTITY
LF	1060

682-6222 CONDUIT, NONMETAL, TP 2, 2 IN	
UNIT	QUANTITY
LF	630

682-6233 CONDUIT, NONMETAL, TP 3, 2 IN	
UNIT	QUANTITY
LF	100650

682-6236 CONDUIT, NONMETAL, TP 2, 2 IN POWER SERVICE	
UNIT	QUANTITY
LF	24845

682-6520 CONDUIT, FIBERGLASS, 2 IN	
UNIT	QUANTITY
LF	10290

682-9028 ELECTRICAL COMMUNICATION BOX TP 5	
UNIT	QUANTITY
EA	75

682-9029 ELECTRICAL COMMUNICATION BOX REHAB	
UNIT	QUANTITY
EA	28

682-9950 DIRECTIONAL BORE - 5 IN	
UNIT	QUANTITY
LF	6760

935-1118 OSP F/O CABLE, LOOSE TUBE, SM, 144 FIBER	
UNIT	QUANTITY
LF	95395

935-1509 OSP F/O CABLE, DROP, SM, 4 FIBER	
UNIT	QUANTITY
LF	135

935-1512 OSP F/O CABLE, DROP, SM, 12 FIBER	
UNIT	QUANTITY
LF	6260

935-3108 F/O CLOSURE, UNDERGROUND, 144 FIBER	
UNIT	QUANTITY
EA	49

935-3601 F/O CLOSURE, FDC, PRE-TERMINATED, TYPE A, 4 FIBER	
UNIT	QUANTITY
EA	1

935-3603 F/O CLOSURE, FDC, PRE-TERMINATED, TYPE A, 12 FIBER	
UNIT	QUANTITY
EA	39

935-4010 F/O SPLICE, FUSION	
UNIT	QUANTITY
EA	1624

935-3408 F/O CLOSURE, FDC (RACK MOUNTED), 144 FIBER*	
UNIT	QUANTITY
EA	4

936-1000 CCTV SYSTEM, TYPE C	
UNIT	QUANTITY
EA	19

937-6000 MICROWAVE RADAR DETECTION ASSEMBLY	
UNIT	QUANTITY
EA	45

937-8020 TESTING - 0011692	
UNIT	QUANTITY
LS	LUMP

939-2237 GBIC, TYPE D	
UNIT	QUANTITY
EA	73

939-2240 GBIC, TYPE E	
UNIT	QUANTITY
EA	11

939-2300 FIELD SWITCH, TYPE A	
UNIT	QUANTITY
EA	33

939-2301 FIELD SWITCH, TYPE B	
UNIT	QUANTITY
EA	7

939-4040 TYPE D CABINET	
UNIT	QUANTITY
EA	16

939-4050 TYPE E CABINET	
UNIT	QUANTITY
EA	1

939-5010 ELECTRICAL POWER SERVICE ASSEMBLY, AERIAL SERVICE POINT	
UNIT	QUANTITY
EA	2

939-8000 TESTING - 0011692	
UNIT	QUANTITY
LS	LUMP

*NOTE:
THE F/O CLOSURE, FDC RACK MOUNTED, 144 FIBERS ARE TO BE INSTALLED IN HUB B AND E (2 IN EACH).

ATKINS

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY
SUMMARY OF QUANTITIES
SR 400 FROM I-85 TO I-285

DRAWING No. 6-001