SUMMARY OF QUANTITIES

VOID

GUARDRAIL QUANTITIES

GUARDRAIL QUANTITIES
GA. STDS. 4380, 4381, 4382, 4385, 4386, 4388

	GUARDRAIL "W" BEAM	GUARDRAIL "T" BEAM	ANCHORAGES	
LOCATION & SIDE	LIN FT	LIN FT	TP 1*	TP 12+
STA 189+97, SR 400 SB	162.5		1	1
STA 190+12, SR 400 NB	162.5		1	1
STA 196+86, SR 400 NB	112.5		1	
STA 207+57, SR 400 SB	162.5		1	1
STA 260+50, SR 400 SB	112.5		1	1
STA 283+10, SR 400 SB	112.5		1	1
STA 295+00, SR 400 NB	87.5		1	1
STA 296+50, SR 400 SB	87.5		1	1
STA 326+89, SR 400 SB	112.5		1	1
STA 406+05, SR 400 SB	150		1	1
STA 444+00, SR 400 NB	112.5		1	1
STA 449+10, SR 400 SB	87.5		1	1
STA 373+00, SR 400 NB	112.5		1	1
AS DIRECTED BY THE ENGINEER	175	150		
TOTALS	1750	150	13	12

* GA. STD. 4383
\+ GA. STD. 4384
NOTE: THE ACTUAL BEGINNING AND ENDING OF GUARDRAIL MAY BE ADJUSTED TO MEET FIELD CONDITION. SEE GA STDS 4380, 4381, 4385, 4386, 4388 FOR DETAILS.

TRAFFIC CONTROL

150-1000 TRAFFIC CONTROL - 0011692	
UNIT	QUANTITY
LS	LUMP

EROSION CONTROL QUANTITIES

PERMANENT EROSION CONTROL

LOCATION	PERMANENT GRASSING	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT	EROSION CONTROL MATS, SLOPES
	ACRE	TON	TON	LB	SY
SR 400	3	9	2	280	-
AS DIRECTED BY ENGINEER	1	1	1	20	3500
TOTAL	4	10	3	300	3500

TEMPORARY EROSION CONTROL

LOCATION	MULCH	CONSTRUCTION EXIT	MAINTENANCE OF CONSTRUCTION EXIT	TEMPORARY SILT FENCE TYPE C	TEMPORARY SILT FENCE TYPE C MAINT.
	TON	EA	EA	LIN FT	LIN FT
SR 400	41	-	-	42000	21000
AS DIRECTED BY ENGINEER	4	4	4	4000	2000
TOTAL	45	4	4	46000	23000

WATER QUALITY MONITORING & SAMPLING

	EACH
0011692 TOTAL	6

WATER QUALITY INSPECTIONS

	MONTHS
0011692 TOTAL	12

ORANGE BARRIER FENCE, 4 FT

TOTAL	1400 LIN FT