| Location No. | Type | Location | Sign Description | Phase | Comments |
|---|---|---|---|---|---|
| 1 | GM | NBGA400 | North GA400 Toll | A | Remove GA400 Toll shield and replace with GA400 shield. |
| 2 | GM | NBGA400 | All Tolls Video Enforced | A | Remove Sign and posts. |
| 3 | GM | NBGA400 | Last Exit Before Toll | D | Remove within 48 hours after conversion. |
| 4 | GM | NBGA400 | North GA400 Toll | A | Remove GA400 Toll shield and replace with GA400 shield. |
| 5 | GM | NBGA400 | All Tolls Video Enforced | A | Remove Sign and posts. |
| 6 | OH | NBGA400 | Toll Plaza 1 mile | B | Remove sign panel and structure in advance of conversion and supplement with PCMS until after conversion. |
| 7 | OH | NBGA400 | Toll Rate Schedule | B | Remove sign panel and structure in advance of conversion. |
| 8.a, 8.b, 8.c | OH | NBGA400 | Toll direction signs and Speed Limit sign | B | Remove sign panels in advance of conversion and supplement with PCMS until after conversion. Retain structure. |
| 9 | OH | NBGA400 | Toll Plaza 1/2 Mile (redundant) | C | Remove sign panel and horizontal arm the night of the conversion. |
| 10 | GM | NBGA400 | Speed Limit 45 mph | E | Remove sign in advance. |
| 11.a, 11.b | OH | NBGA400 | Toll direction signs | B | Remove sign panels and structure in advance of conversion and supplement with PCMS until after conversion. |
| 12 | GM | NBGA400 | Handicap Pay Toll Assistance Right Lane | B | Remove Sign and post. |
| 13 | OH | NBGA400 | Toll Rate Schedule | C | Remove sign panel and structure the night of the conversion. |
| 14.a, 14.b, 14.c | OH | NBGA400 | Toll direction signs | B | Remove sign panels and structure in advance of conversion and supplement with PCMS until after conversion. |
| 15 | GM | NBGA400 | Trucks Trailers Right Lane | B | Remove Sign and posts. |
| 16 | OHM - Structure | SBGA400 | GA400 Toll Buckhead/Atlanta with "Toll Road" plaque | X | Replace GA400 Toll shield with GA400 shield and remove or overlay "Toll Road" with blank panel. |
| 17 | GM | SBGA400 | Last Exit Before Toll | D | Remove within 48 hours after conversion |
| 18 | GM | SBGA400 | All Tolls Video Enforced | A | Remove Sign and posts. |
| 19 | GM | SBGA400 | All Tolls Video Enforced | A | Remove Sign and posts. |
| 20 | GM | SBGA400 | South GA400 Toll | A | Replace GA400 Toll shield with GA400 shield. |
| 21 | OH | SBGA400 | Toll Plaza 1 mile | B | Remove sign panel and structure in advance of conversion and supplement with PCMS until after conversion. |
| 22 | OH | SBGA400 | Toll Rate Schedule | B | Remove sign panel and structure in advance of conversion . |
| 23 | GM | SBGA400 | Reduced Speed Ahead | E | Remove sign and post in advance. |
| 24 | GM | SBGA400 | Trucks Trailers Right Lane | B | Remove Sign and post. |
| 25.a, 25.b, 25.c | OH | SBGA400 | Toll direction signs and Speed Limit sign | B | Remove sign panels and structure in advance of conversion and supplement with PCMS until after conversion. |
| 26 | OH | SBGA400 | Toll Plaza 1/2 Mile (redundant) | C | Remove sign panel the night of the conversion. Retain structure. |
| 27 | GM | SBGA400 | Speed Limit 45 mph | E | Remove sign and posts in advance. |
| 28 | GM | SBGA400 | Handicap Pay Toll Assistance Right Lane | B | Remove Sign and posts. |
| 29.a, 29.b | OH | SBGA400 | Toll direction signs | B | Remove sign panels and horizontal member and left vertical support of structure in advance of conversion and supplement with PCMS until after conversion. |
| 30 | OH | SBGA400 | Toll Rate Schedule | C | Remove sign panel and horizontal arm the night of the conversion. |
| 31.a, 31.b, 31.c | OH | SBGA400 | Toll direction signs | B | Remove sign panels and structure in advance of conversion and supplement with PCMS until after conversion. |
| 32 | OHM - Structure | N on I-85 | GA400 Buckhead/Cumming with "Toll Road" plaque | X | Sign and structure to be replaced by Project M0004427. |
| 33 | OHM - Structure | N on I-85 | GA400 Toll Buckhead/Cumming | E | Replace GA400 Toll shield with GA400 shield. |
| 34 | OHM - Structure | N on I-85 | GA400 Buckhead/Cumming with "Toll Road" plaque | X | Signs and structure to be replaced by Project M0004427. |
| 35 | GM | I-85 ramp to GA400 | North GA400 Toll | A | Replace GA400 Toll shield with GA400 shield. |
| 36 | GM | ramp onto GA400 | All Tolls Video Enforced | A | Remove Sign and posts. |
| 37 | OHM - Structure | N on Spring Buford Conn | GA400 Toll (Lg) North, Left 1 Mile | E | Replace GA400 Toll shield with GA400 shield. |
| 38 | OHM - Structure | N on Spring Buford Conn | GA400 Toll (Lg) North, Left 1/4 Mile | E | Replace GA400 Toll shield with GA400 shield. |
| 39 | GM | N on Buford Hwy | To North GA400 Toll | E | Replace GA400 Toll shield with GA400 shield. |

| Location No. | Type | Location | Sign Description | Phase | Comments |
|---|---|---|---|---|---|
| 40 | GM | S on Buford Hwy | North GA400 Toll | E | Replace GA400 Toll shield with GA400 shield. |
| 41 | OHM - Structure | S on Buford Hwy | GA237 GA400 Toll (Sm) Sidney Marcus/Piedmont Rd | E | Replace GA400 Toll shield with GA400 shield. |
| 42 | GM | W on Sidney Marcus Blvd towards 400 N | Junction North GA400 Toll | E | Replace GA400 Toll shield with GA400 shield. |
| 43 | OHM - Span Wire | W on Sidney Marcus Blvd towards 400 N | GA400 Toll N (Sm) | E | Replace GA400 Toll shield with GA400 shield. |
| 44 | GM | E on Sidney Marcus Blvd towards 400 N | North GA400 Toll with "Toll Road" panel | E | Replace all signs. |
| 45 | OHM - Span Wire | E on Sidney Marcus Blvd towards 400 N | GA400 Toll N (Sm) | E | Replace all signs. |
| 46 | OHM - Span Wire | W on Lenox Rd towards GA400 | To GA400 Toll (Sm) | E | Replace all signs. |
| 47 | GM | W on Lenox Rd towards GA400 | Junction GA400 Toll with "peach pass panel" | E | Replace GA400 Toll shield with GA400 shield. Remove "Peach Pass" panel. |
| 48.a | OHM - Span Wire | W on Lenox Rd towards 400 S | GA400 Toll S (Sm) | E | Replace all signs. |
| 48.b | OHM - Span Wire | W on Lenox Rd towards 400 N | GA400 Toll N (Sm) | E | Replace all signs. |
| 49 | OHM - Span Wire | N on Piedmont Rd towards Lenox Rd | To GA400 Toll (Sm) | E | Replace all signs. |
| 50 | OHM - Span Wire | S on Piedmont Rd towards Lenox Rd | To GA400 Toll (Sm) | E | Replace all signs. |
| 51.a | OHM - Span Wire | E on Lenox Rd towards 400 N | GA400 Toll N (Sm) | E | Replace all signs. |
| 51.b | OHM - Span Wire | E on Lenox Rd towards 400 S | GA400 Toll S (Sm) | E | Replace all signs. |
| 52 | GM | W on Glenridge Con towards GA400 S | Junction GA400 with "Toll Road" panel | E | Remove "Toll Road" panel. |
| 53 | OHM - Span Wire | W on Glenridge Con towards GA400 S | GA400 Toll S (Sm) | E | Replace all signs. |
| 54 | OHM - Span Wire | W on Glenridge Con towards GA400 S | GA400 Toll S (Sm) | E | Replace all signs. |
| 55 | GM | E on Glenridge Con towards GA400 S | Junction GA400 with "Toll Road" panel | E | Remove "Toll Road" panel. |
| 56 | OHM - Span Wire | E on Glenridge Con towards GA400 S | GA400 Toll S (Sm) | E | Replace all signs. |
| 57 | GM | E on Glenridge Con towards GA400 S | South GA400 Toll | E | Replace GA400 Toll shield with GA400 shield. |
| 58 | OHM - Structure | Access Road adjacent to GA400 S | GA400 Toll (Lg) Buckhead/Atlanta | E | Replace GA400 Toll shield with GA400 shield. |
| 59 | OHM - Structure | W on I-285 to GA400 | GA400 Toll (Lg) Atlanta with "Toll Road" plaque | X | Replace GA400 Toll shield with GA400 shield and remove or overlay "Toll Road" with blank panel. |
| 60 | OHM - Structure | W on I-285 to GA400 | GA400 Toll (Lg) Atlanta with "Toll Road" plaque | X | Replace GA400 Toll shield with GA400 shield and remove or overlay "Toll Road" with blank panel. |
| 61 | OHM - Structure | W I-285 ramp onto GA400 South | GA400 Toll (Lg) Buckhead/Atlanta with "Toll Road" plaque | X | Replace GA400 Toll shield with GA400 shield and remove or overlay "Toll Road" with blank panel. |
| 62 | OHM - Structure | E I-285 ramp onto GA400 South | GA400 Toll (Lg) Buckhead/Atlanta with "Toll Road" plaque | X | Replace GA400 Toll shield with GA400 shield and remove or overlay "Toll Road" with blank panel. |
| 63 | GM | E I-285 ramp onto GA400 South | All Tolls Video Enforced | A | Remove Sign and posts. |
| 64 | OHM - Structure | West Peachtree St at Peachtree St | I-85 North, GA 13 North, GA 400 Toll North, Buford Highway | E | Replace GA400 Toll shield with GA400 shield. |
| 65 | GM | Monroe Dr at Piedmont Circle | To GA400 Toll (Sm) | E | Replace GA400 Toll shield with GA400 shield. |
| 66 | GM | SB Peachtree St at ramp to GA 13 NB | To GA400 Toll (Sm) | E | Replace GA400 Toll shield with GA400 shield. |

| | |
|---|---|
| A | 4-6 weeks in advance of conversion (redundant signs) |
| B | 2-3 weeks in advance of conversion (redundant signs, toll rate schedule) |
| C | Night or day of conversion |
| D | Within 48 hours after conversion |
| E | Within 2 weeks after conversion |
| X | 1 week in advance of conversion |
| | |
| OH | Overhead Removal |
| GM | Ground Mounted |
| OHM | Overhead Modified |

VOID

ATKINS

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION

OFFICE:

**SIGNING AND MARKING PLANS**
**SIGN INVENTORY INDEX**

GA 400 TOLL PLAZA
DEMOLITION & GP LANES CONVERSION

DRAWING No. 26-002