CONSTRUCTION PLANS

FOR CONSTRUCTION OF

POLK COUNTY AIRPORT

CEDARTOWN, GEORGIA

SUMMARY OF QUANTITIES

NO.	ITEM NO.	ITEM	QUANTITIES	UNIT
1	P-151	CLEARING	30	AC.
2	P-151	CLEARING AND GRUBBING	18	AC.
3	P-152	UNCLASSIFIED EXCAVATION	124,978	C.Y.
4	P-154	SUB BASE COURSE	5613	C.Y.
5	P-213	SAND CLAY BASE	6564	C.Y.
6	P-401	AGGREGATE BITUMINOUS SURFACE COURSE	1743	TONS
7	P-401	BITUMINOUS MATERIAL	23,910	GAL.
8	P-405	KEYSTONE MAT COURSE	35642	S.Y.
9	P-602	BITUMINOUS PRIME COAT	7,127	GAL.
10	P-603	BITUMINOUS TACK COAT	1783	GAL.
11	P-620	RUNWAY & TAXIWAY MARKING	4,490	S.F.
12	D-702	18" R.C.P. DRAIN PIPE	56	L.F.
13	D-752	HEADWALLS FOR 18" DRAIN	2	EA.
14	T-901	SEEDING	22	AC.
15		SEGMENTED CIRCLE & WIND CONE	1	EA.
16	L-110	2 WAY 4" UG ELECTRICAL DUCT	127	L.F.
20	L-122	LOW INTENSITY LIGHTING SYSTEM	1	EA.
		ALTERNATES		
17	P-301	SOIL CEMENT BASE	35,642	S.Y.
18	P-301	PORTLAND CEMENT	4640	BBL.
19	D-703	18" - 16 GAGE C.C.M. PIPE	56	L.F.
		AUTO PARKING (NON FAAP)		
21	P-152	UNCLASSIFIED EXCAVATION	1,437	C.Y.
22	P-154	SUB BASE COURSE	57	C.Y.
23	P-213	SAND CLAY BASE	66	C.Y.
24	P-401	AGG BIT SURFACE COURSE	17	TONS
25	P-401	BIT MATERIAL	2490	GAL.
26	P-405	KEYSTONE MAT	333	S.Y.
27	P-602	BIT PRIME COAT	66	GAL.
28	P-603	BIT TACK COAT	17	GAL.
29	P-301	SOIL CEMENT BASE	333	S.Y.
30	P-301	PORTLAND CEMENT	37	BBL

APPROVED BY

DATE

FAAP PROJECT NO. 9-09-056- -01

BOARD OF COMMISSIONERS OF ROADS AND REVENUES

M. M. CORNELIUS, CHAIRMAN
R. LYLE BOND, VICE CHAIRMAN
SAM B. ALBEA, JR., MEMBER
WILEY J. CASEY, MEMBER
ELMO Z. PEPPERS, MEMBER
GEORGE H. REYNOLDS, MEMBER

PREPARED BY

HENSLEY-SCHMIDT, INC.
CONSULTING ENGINEERS
MARIETTA, GA. CHATTANOOGA, TENN.

APPROVED BY

SAM P. HENSLEY

DATE

INDEX

TITLE	DWG. NO.
TITLE SHEET AND INDEX AND SUMMARY OF QUANTITIES	1
LOCATION AND VICINITY MAPS	2
APPROACH PLAN	3
PROPERTY MAP (NOT INCLUDED IN THIS SET)	4
AIRPORT LAYOUT PLAN	5
CONSTRUCTION LAYOUT PLAN	6
CLEARING AND GRUBBING	7
GRADING AND DRAINAGE PLAN	8
DRAINAGE DETAILS	9
MARKING AND SEEDING PLAN	10
MISCELLANEOUS DETAILS	11
LOG OF BORINGS	12 & 13
RUNWAY PLAN AND PROFILE	14 & 15
RUNWAY CROSS-SECTIONS	16 – 20
TAXIWAY AND ACCESS ROAD PLAN AND PROFILE	21
TAXIWAY AND APRON CROSS-SECTIONS	22
ACCESS ROAD CROSS-SECTIONS	23
LIGHTING PLAN	24
LIGHTING DETAILS	25