



SPECIAL NOTE:
GENERAL USE OF THESE DETAILS WILL BE WHERE FILL EMBANKMENT WARRANTS GUARDRAIL AND PAVED SHOULDER WILL BE ADJACENT TO THE ROADWAY. OMIT ON HIGH SIDE OF S.E.


NOTE:
WHEN THE 10"x10"x6" 45 WYE IS A REQUIRED PART OF STAGE 1 CONSTRUCTION, A TEMPORARY PLUG WILL BE REQUIRED FOR THE 6" BRANCH OF THE WYE UNTIL THE CONNECTION OF THE PERFORATED PIPE IS MADE ON STAGE 2 CONSTRUCTION. SEE SECTION 577

DETAIL OF ASPHALTIC CONCRETE CURB (TYP.)




APRON QUANTITY:
0.17 CU. YDS. CL. "B" CONCRETE OR CL. "A" CONCRETE


ALTERNATE:
APRON MAY BE CONSTRUCTED TO APPROXIMATELY THE SAME MIN. DIMENSIONS FROM SAND CEMENT BAG RIP RAP, STONE GROUT RIP RAP, OR MORTAR RUBBLE MASONRY WITH NO CHANGE IN PAYMENT.



- GENERAL NOTES:**
- SEE DETAIL SHEET "SHOULDER PAVING & SURFACING UNDER GUARDRAIL" FOR REQUIREMENTS FOR TREATMENT UNDER GUARDRAIL.
 - CONTRACTOR MAY ELECT TO USE SLOPE DRAIN PIPE WITH LARGER DIAMETER THAN 10" WITH NO ADDITIONAL PAYMENT. METAL DRAIN INLET WILL BE MODIFIED FOR APPROVED CONNECTION TO THE LARGER SLOPE DRAIN PIPE, WITH NO ADDITIONAL PAYMENT.
 - SPECIFICATIONS: GEORGIA STANDARD, CURRENT EDITION AND SUPPLEMENTS THERETO. SEE SECTION 577 FOR STAGE CONSTRUCTION.
 - SPILLWAY MAY BE CONSTRUCTED USING CONCRETE (SECTION 441) AT CONTRACTOR'S OPTION WITH NO ADDITIONAL PAYMENT.




FRONT VIEW



SIDE VIEW

DETAILS OF METAL DRAIN INLET



TOP VIEW

NOTE: DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES.

DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA			
CONSTRUCTION DETAIL ASPHALTIC CONCRETE SPILLWAY WITH METAL DRAIN INLET ASPHALTIC CONCRETE CURB			
NO SCALE			DEC. 1995
GENERAL REVISIONS	DATE		
4-28-99	03-22-99		
GENERAL REVISIONS	DATE		
12-19-96			
DES. _____	(SUBMITTED) _____		
DRW. _____	(APPROVED) _____		
TR. _____	_____		
CHK. _____	_____		
		NUMBER D-26	