STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NH000-0038-01(040)		

210-0100
GRADING COMPLETE
NH000-0038-01(040) LUMP

150-1000
TRAFFIC CONTROL
NH000-0038-01(040) LUMP

634-1200
CONCRETE RIGHT-OF-WAY MARKER - STD 9003
166 EA

318-3000
AGGREGATE SURFACE COURSE
AS REQUIRED 1500 TONS

432-5010
MILL ASPHALTIC CONCRETE PAVEMENT VARIABLE DEPTH (SY)*
6720 SY

* AS DIRECTED BY THE ENGINEER

573-2006 UNDERDRAIN PIPE INCLUDING DRAINAGE AGGREGATE,6 IN *
4500 LF

* AS DIRECTED BY THE ENGINEER

643-8200
BARRIER FENCE (ORANGE),4 FT
1550 LF

FIELD ENGINEER'S OFFICE- TYPE 3
153-1300 | 1 EACH

ROADWAY

LOCATION	402-3103 RECYCLED ASPH. CONC 9.5mm SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (TN)	402-3190 RECYCLED ASPH. CONC 19mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME (TN)	402-3121 RECYCLED ASPH. CONC 25mm SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (TN)	402-1812 RECYCLED ASPH. CONC LEVELING, INCL BITUM MATL & H LIME (TN)	310-1101 GRADED AGGREGATE BASE (TN)	318-3000 AGGREGATE SURFACE COARSE (TN)	413-1000 BITUM TACK COAT (GL)
SR 4/ US1	5055	4710	11775	3390	28260	0	4832
SIDEROADS	294	214	0	110	1025	484	174
SHOULDERS	490	799	0	0	3905	0	291
DRIVES	255	665	0	0	0	0	152
TOTAL	6094	6388	11775	3500	33190	484	5449

446-1100
PAVEMENT REINFORCING FABRIC STRIPS,TP 2,18 INCH WIDTH

LOCATION	SIDE	LF
STA 200+64 TO 301+41	LT	10,077
STA 200+64 TO 301+41	RT	10,077
AS DIRECTED BY THE ENGINEER		20,000
TOTAL		40,154

455-1000
FILTER FABRIC FOR EMBANKMENT STABILIZATION (SY)*
36,000 SY

* AS DIRECTED BY THE ENGINEER

CONCRETE ITEMS

	ITEM	QUANTITY
441-0016	DRIVEWAY CONCRETE 6 IN THICK (SY)	114
441-0018	DRIVEWAY CONCRETE 8 IN THICK (SY)	353
441-4020	CONCRETE VALLEY GUTTER 6 IN (SY)	35
441-4030	CONCRETE VALLEY GUTTER 8 IN (SY)	542
441-0104	CONCRETE SIDEWALK 4 IN (SY)	2585
441-0108	CONCRETE SIDEWALK 8 IN (SY)	170
441-6222	CONCRETE CURB AND GUTTER, 8 IN X 30 IN, TYPE 2 (LF)	5250
441-3999	CONCRETE V GUTTER (LF)	409
441-0303	CONCRETE SPILLWAY, TP 3 (EA)	3
500-3200	CLASS B CONCRETE (CY)	0.334
500-9999	CLASS B CONCRETE, BASE OR PAVEMENT WIDENING (CY)	145
441-0740	CONCRETE MEDIAN, 4 IN (SY)	117
444-1000	SAWED JOINTS IN EXIST PAVEMENTS-PCC (LF)	116

456-2015
INDENTATION RUMBLE STRIPS - GROUND-IN-PLACE (SKIP)
3 GLM

643-0104 **FENCE SUMMARY**

STATION TO STATION	SIDE	CHAIN LINK 4'	FIELD FENCE WOVEN WIRE CONSTR. USING STEEL POSTS DETAIL F4 — 1 STND BARBED WIRE, TOP, LIN. FT. 4'	FIELD FENCE BARBED WIRE, 4 STRANDS 4'	REMOVE & RESET GATES (12')	REMOVE & RESET GATES (15')
		LF	LF	LF	EACH	EACH
S.R. 4	—					
STA. 231+01 TO STA. 232+25.93	LEFT			164		
TOTAL	—			164		

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W AND LIMIT OF ACCESS

SCALE IN FEET
0 50 100 200

DATE	REVISIONS	DATE	REVISIONS

Wed Jul 30 14:45:36 2014
Wed Jul 30 14:45:36 2014

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT: NH000-0038-01(040)
COUNTY: EMANUEL
DRAWING NO. 06-001