STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NH000-0038-01(040)		

SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	CODE	SIGNS (SQUARE FEET) TYPE 3 REFLECTIVITY 636-1020 SIZE	QTY	TYPE I (0.08) SQUARE FEET	636-1029 SIZE	QTY	TYPE 2 (0.10) SQUARE FEET	636-1033 SIZE	QTY	TYPE 9 REFLECTIVITY TYPE I (0.08) SQUARE FEET	636-1041 SIZE	QTY	TYPE 2 (0.10) SQUARE FEET	POSTS (LINEAR FEET) 636-2070 TYPE 7 LENGTH	QTY	LINEAR FEET	636-2080 TYPE 8 LENGTH	QTY	LINEAR FEET	636-2090 TYPE 9 LENGTH	QTY	LINEAR FEET
SR 4/US 1																							
FIELD	1	OM-3R							12 X 36	1	3				14	1	14						
FIELD	2	W1-7							48 X 24	1	8				13	1	13						
FIELD	3	OM-3L							12 X 36	1	3				14	1	14						
203+60 RT	4	M3-1	24 X 12	1	2													14	1	14			
		M1-4	24 X 24	1	4																		
		M1-5	24 X 24	1	4																		
205+00 RT	5	D2-1	78 X 12	1	6.5										13.5	1	13.5						
206+58 RT	6	R2-1	24 X 30	1	5																		
250+68 RT	8	W2-1							36 X 36	1	9										17.25	2	34.50
		W16-8A							54 X 24	1	9												
252+74 RT	9	D10-1	10 X 18	1	1.25										12.5	1	12.5						
258+85 RT	10	R1-2							36X36X36	1	4				13.5	1	13.5						
258+50 RT	11	R1-1							36 X 36	1	9				14	1	14						
274+14 RT	12	W2-1							36 X 36	1	9										17.25	2	34.50
		W16-8A										60 X 24	1	10									
281+95 RT	13	R1-1							36 X 36	1	9				14	1	14						
282+23 RT	14	R1-2							36X36X36	1	4				13.5	1	13.5						
283+50 RT	15	R2-1	24 X 30	1	5										13.5	1	13.5						
297+00 RT	16	W2-3L							36 X 36	1	9										16.25	1	16.25
		W16-8A							48 X 12	1	4												
300+96 RT	17	I-2	48 X 24	1	8										13	1	13						
302+22 RT	18	I550-1	30 X 36	1	7.5										14	1	14						
303+28 RT	19	OM-3L							12 X 36	1	3				14	1	14						
303+33 RT	20	W1-7							48 X 24	1	8				13	1	13						
303+38 RT	21	OM-3R							12 X 36	1	3				14	1	14						
304+20 LT	22	R1-2							36X36X36	1	4				13.5	1	13.5						
303+57 LT	23	R1-1							36 X 36	1	9				14	1	14						
289+15 LT	24	W2-1							36 X 36	1	9										17.25	2	34.50
		W16-8A										60 X 24	1	10									
281+95 LT	25	R1-2							36X36X36	1	4				13.5	1	13.5						
281+29 LT	26	R1-1							36 X 36	1	9				14	1	14						
281+04 LT	27	R2-1	24 X 30	1	5										13.5	1	13.5						
285+68 LT	28	W2-1							36 X 36	1	9										17.25	2	34.50
		W16-8A							54 X 24	1	9												
257+91 LT	29	R1-1							36 X 36	1	9				14	1	14						
257+60 LT	30	R1-2							36X36X36	1	4				13.5	1	13.5						
208+34 LT	31	M2-1	21 X 12	1	1.75													14	1	14			
		M1-4	24 X 24	1	4																		
		M1-5	24 X 24	1	4																		
206+45 LT	32	W3-1A							36 X 36	1	9				15.25	1	15.25						
205+25 LT	33	D1-3				66 X 36	1	16.5															
204+00 LT	34	M3-3	24 X 12	1	2													18	2	36	14	2	28
		M1-4	24 X 24	1	4																		
		M1-5	24 X 24	1	4																		
		M6-1L	21 X 15	1	2.1875																		
		M3-1	24 X 12	1	2																		
		M1-4	24 X 24	1	4																		
		M1-5	24 X 24	1	4																		
		M6-1R	21 X 15	1	2.1875																		
201+72 LT	35	M4-6	24 X 12	1	2													15.25	2	30.50			
		M1-4	24 X 24	1	4																		
		M1-5	24 X 24	1	4																		
201+12 LT	36	R1-2							36X36X36	1	4				13.5	1	13.5						
200+86 LT	37	R1-1							36 X 36	1	9							16	1	16			
212+00 LT	38	R6-3A	30 X 24	1	5				36 X 36	1	9							16	1	16			
203+80 LT	39	W1-2R													14	1	14						
		R3-7R	30 X 30	1	6.25																		
QUICK ROAD																							
78+50 LT	40	R1-1							36 X 36	1	9				14	1	14						
78+00 LT	41	W3-1A							36 X 36	1	9							16	1	16			
INJUNCTION RD																							
13+41 LT	42	W3-1A							36 X 36	1	9				15.25	1	15.25						
MIXON RD																							
52+60 LT	43	W3-1A							36 X 36	1	9				15.25	1	15.25						
TOTALS				26	103.625	1	16.5		33		227	2		20	29		386.75	9		142.50	13		206.25

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W AND LIMIT OF ACCESS

SCALE IN FEET
0 50 100 200

DATE	REVISIONS	DATE	REVISIONS

Wed Jul 30 14:45:08 2014
Wed Jul 30 14:45:08 2014

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PROJECT: NH000-0038-01(040)
COUNTY: EMANUEL

DRAWING No. 06-004