STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NH000-0038-01(040)		

EROSION CONTROL QUANTITIES	TEMPORARY																	PERMANENT					
	163-0232 TEMPORARY GRASSING	163-0240 MULCH	163-0542 CONST & REM STONE FILTER RING	165-0111 MAINTENANCE OF STONE FILTER RING	171-0030 TEMPORARY SILT FENCE, TYPE "C"	165-0030 MAINTENANCE OF SILT FENCE, TYPE "C"	167-1000 WATER QUALITY MONITORING & SAMPLING	167-1500 WATER QUALITY INSPECTIONS	163-0300 CONSTRUCTION EXIT	165-0101 MAINTENANCE OF CONSTRUCTION EXIT		165-0041 MAINTENANCE OF EROSION CHECK DAMS ALL TYPES	163-0527 CONST AND REM RIP RAP CHECK DAMS	163-0550 CONSTRUCT & REMOVE INLET SEDIMENT TRAP	165-0105 MAINTENANCE OF INLET SEDIMENT TRAP	163-0503 CONST & REMOVE SILT CONTROL GATE, TP 3	165-0087 MAINTENANCE OF SILT CONTROL GATE, TP 3	700-6910 PERMANENT GRASSING	700-8000 FERTILIZER MIXED GRADE	700-7000 AGRICULTURAL LIME	700-8100 FERTILIZER NITROGEN CONTENT	716-2000 EROSION CONTROL SLOPE MATS	711-0100 TURF REINFORCING MATTING, TP 1
	ACRE	TON	EA	EA	LF	LF	EA	MONTHS	EA	EA		LF	EA	EA	EA	EA	EA	ACRE	TON	TON	LB	SQ. YD.	SQ. YD.
S.R. 4 / U.S. 1	36	432	10	10	26732	13366	2	18	10	20		6550	655	23	23	10	10	36	45	108	3600	16,800	2225
TOTAL	36	432	19	19	26732	13366	2	18	10	20		6550	655	23	23	10	10	36	45	108	3600	16,800	2225

163-0520
CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN*

LOCATION	LF
S.R. 4 / U.S. 1	2260
TOTAL	2260

* AS REQUIRED

163-0529 AS DIRECTED BY THE ENGINEER
CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM
1200 LF

165-0071
MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW
600 LF
AS DIRECTED BY THE ENGINEER

207-0203
FOUND BKFILL MATL,TP II
40 CY
AS DIRECTED BY THE ENGINEER

163-0541
CONSTRUCT AND REMOVE ROCK FILTER DAMS
20 EA
AS DIRECTED BY THE ENGINEER

165-0110
MAINTENANCE OF ROCK FILTER DAM
20 EA
AS DIRECTED BY THE ENGINEER

711-0100 DITCH PROTECTION

LOCATION STA TO STA	SIDE	WIDTH FT	DEPTH OF PROTECTION FT	TURF REINFORCING MATTING,TP I SQ YD
239+00 TO 245+00	RT	10.0	1.0	700
254+00 TO 258+00	RT	10.0	1.0	500
129+50 TO 134+40	LT	9.0	1.0	512.5
129+50 TO 134+40	RT	9.0	1.0	512.5
TOTAL				2225

* FOR INFORMATION ONLY

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W AND LIMIT OF ACCESS

SCALE IN FEET
0 50 100 200

DATE	REVISIONS	DATE	REVISIONS

Wed Jul 30 14:44:55 2014
Wed Jul 30 14:44:55 2014

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
PROJECT: NH000-0038-01(040)
COUNTY: EMANUEL
DRAWING No. 06-006

CPDOT 7/30/2014 2:44:53 PM \\GDOT-DSN1\GOPLOT\QCF\d2_PDF_Out_mono_200dpi.qcf fgrimes O:\Emanuel\222630 Emanuel Co\Microstation\222630_06-006.prf D2-Teppille