

---

**GENERAL NOTES (CONTINUED)**

---

11. REPLACE RUMBLE STRIPS AT THE INTERSECTION WITH SR 1, LOG 0.069, SR 38, LOG 14.4, OLD WHIGHAM RD/CR 416, LOG 16.895 AND SR 97, LOG 28.424, IN ACCORDANCE WITH SECTION 429 OF THE SPECIFICATIONS.
12. ALL SHOULDER AREAS WITHIN THE LIMITS OF THE ASPHALT SHOULDER WIDENING OPERATION, WHERE INSUFFICIENT SHOULDER WIDTH EXISTS TO ACCOMMODATE THE ASPHALT SHOULDER WIDENING, SHALL BE CONSTRUCTED TO THE NECESSARY WIDTH BY THE GEORGIA D.O.T. MAINTENANCE FORCES. NOTIFICATION OF THE ENGINEER PRIOR TO BEGINNING WORK IS REQUIRED.
13. APPLY SOIL STERILANT IN ACCORDANCE WITH SPECIFICATION 725 AT THE JOINT FACE PRIOR TO APPLICATION OF THE TACK COAT FOR SHOULDER WIDENING OPERATIONS. THE COST OF THIS WORK WILL BE INCLUDED IN THE OVERALL BID PRICE.
14. REMOVE ANY EXISTING ASPHALT SHOULDER PAVING PRIOR TO CONSTRUCTING NEW ASPHALT SHOULDER WIDENING AND DISPOSE OF THE REMOVED MATERIALS, INCLUDING MATERIAL EXCAVATED FOR THE SHOULDER WIDENING, OFF THE RIGHT-OF-WAY. THE COST OF THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE.
15. APPLY SOIL STERILANT IN ACCORDANCE WITH SPECIFICATION 725 AT THE JOINT OF EXISTING WIDENED SECTIONS PRIOR TO APPLICATION OF THE TACK COAT. THE COST OF THIS WORK WILL BE INCLUDED IN THE OVERALL BID PRICE.
16. RESTRIPE ALL EXISTING ROADWAY MARKINGS AT EXISTING LOCATIONS ON ROADWAY AND AS CURRENTLY MARKED WITH THE EXCEPTION OF CROSSWALKS. EXISTING CROSSWALKS SHALL BE STRIPED IN ACCORDANCE WITH CROSSWALK DETAIL. RESTRIPE ALL EXISTING ROADWAY MARKINGS ON SIDE ROADS TO THE END OF THE NEW RESURFACED SECTION. ALSO, RESTRIPE OR PAINT (WHERE NOT EXISTING) STOP BARS AT ALL PAVED SIDE ROADS AND STREETS. REFERENCE PAVEMENT MARKING DETAILS AND NOTES IN THE PLANS FOR LOCATING EDGE LINES.
17. TEMPORARY STRIPING IS REQUIRED IN ACCORDANCE WITH SECTION 150.04 OF THE GEORGIA SPECIFICATIONS. PLACEMENT OF PERMANENT PAVEMENT MARKINGS SHALL NOT BEGIN UNTIL FINAL SURFACE COURSE HAS BEEN COMPLETED FOR THIRTY (30) CALENDAR DAYS AND WILL BE COMPLETED WITHIN FORTY-FIVE (45) CALENDAR DAYS AFTER THE FINAL SURFACE COURSE HAS BEEN COMPLETED. FAILURE TO PLACE PERMANENT PAVEMENT MARKINGS AS SPECIFIED WILL RESULT IN LIQUIDATED DAMAGES TO BE ASSESSED IN ACCORDANCE WITH SUBSECTION 108.08 OF THE SPECIFICATIONS.
18. PLACE PREFORMED PAVEMENT MARKINGS ON ALL CONCRETE BRIDGE DECKS IN ACCORDANCE TO THE DEPARTMENT'S SPECIFICATION SECTION 657. IT WILL BE REQUIRED TO REMOVE 90 PER CENT OF THE EXISTING DECK STRIPING PRIOR TO PLACEMENT OF PREFORMED PAVEMENT MARKINGS. PAYMENT OF THIS WORK SHALL BE INCLUDED IN THE OVERALL BID OF SECTION 657.